

F.A.S. RTE. 2466	SECTION (1)RS-3	COUNTY WOODFORD	TOTAL SHEETS 23	SHEET NO. 11
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

EPOXY PAVEMENT MARKINGS						
LOCATION	4" YELLOW FEET	4" WHITE FEET	6" WHITE FEET	12" WHITE FEET	24" WHITE FEET	LETTER & SYMBOLS SQ FT
Sta. 193+74 - 209+25	441	3,102				
Sta. Eq. 209+25 = 209+30						
Sta. 209+30 - 263+99.2	8,465.40	10,938.40				
Sta. Eq. 263+99.2 - 263+98.8						
Sta. 263+98.8 - 283+91.05	2,384.50	3,984.50				
Sta. Eq. 283+91.05 = 283+57.65						
Sta. 283+57.65 - 284+72	228.7	228.7				
Bridge Omission 284+72 - 289+05						
Sta. 289+05 - 326+00	5,396.60	7,390				
Sta. Eq. 326+00 = 1043+44.14						
Sta. 1043+44.14 - 1096+42	7,218.52	10,595.72			33	61.2
R. R. Omission 1096+42 - 1096+70						
Sta. 1096+70 - 1121+64	1,437.68	4,988	44	70	33	61.2
Sta. Eq. 1121+64 = 0+00						
Sta. 0+00 - 132+41.6	7,412.15	26,483	44	70		
Sta. Eq. 132+41.6 = 137+54.9						
Sta. 137+54.9 - 171+90.3	5,234	6,870.80				
Sta. Eq. 171+90.3 - 171+97.7						
Sta. 171+97.7 - 244+62	7,351.30	14,528.60				
TOTAL	45,570	89,110	88	140	66	122.4
	134,680					

TEMPORARY PAVEMENT MARKINGS						
LOCATION	4" YELLOW FEET	4" WHITE FEET	6" WHITE FEET	12" WHITE FEET	24" WHITE FEET	LETTER & SYMBOLS SQ FT
Sta. 193+74 - 209+25	441	3,102				
Sta. Eq. 209+25 = 209+30						
Sta. 209+30 - 263+99.2	8,465.40	10,938.40				
Sta. Eq. 263+99.2 - 263+98.8						
Sta. 263+98.8 - 283+91.05	2,384.50	3,984.50				
Sta. Eq. 283+91.05 = 283+57.65						
Sta. 283+57.65 - 284+72	228.7	228.7				
Bridge Omission 284+72 - 289+05						
Sta. 289+05 - 326+00	5,396.60	7,390				
Sta. Eq. 326+00 = 1043+44.14						
Sta. 1043+44.14 - 1096+42	7,218.52	10,595.72			33	61.2
R. R. Omission 1096+42 - 1096+70						
Sta. 1096+70 - 1121+64	1,437.68	4,988	44	70	33	61.2
Sta. Eq. 1121+64 = 0+00						
Sta. 0+00 - 132+41.6	7,412.15	26,483	44	70		
Sta. Eq. 132+41.6 = 137+54.9						
Sta. 137+54.9 - 171+90.3	5,234	6,870.80				
Sta. Eq. 171+90.3 - 171+97.7						
Sta. 171+97.7 - 244+62	7,351.30	14,528.60				
TOTAL	45,570	89,110	88	140	66	122.4
	134,680					

PATCHING SCHEDULE			
LOCATION	TYPE 2 SQ YD	TYPE 3 SQ YD	TYPE 4 SQ YD
Sta. 193+74 - MABLE DRIVE	403.2	211.2	32
MABLE DR. - GRIMM RD	118.4		
GRIMM RD - IRON RD	73.6		
IRON RD - REABA RD	44.8		
REABA RD - SHARP RD	77.6		
SHARP RD - MACALLEN LAKE RD	25.6		
MACALLEN LAKE RD - TR 2000E	28.8		
TR 2000E - HUDSON RD			192
TOTAL	772	211	224

SHORT TERM PAVEMENT MARKING	
LOCATION	FEET
Sta. 193+74 to 284+72	830
Sta. 289+05 to 1096+42	818
Sta. 1096+70 to 244+62	2,403
Total	4,051
3 Application (Milled, Binder & Surface)	
3 x 4,051	12,153
TOTAL	12,153

SCHEDULE OF QUANTITIES