

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	*	PEORIA	22	6
STA. 215+18.77		TO STA. 246+46.02		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				
* D4 JOINT REPAIR 2007-3				

SCHEDULE OF QUANTITIES

REINFORCEMENT BARS = 8050 POUND			
PEORIA COUNTY		TAZEWELL COUNTY	
L4	805 POUND	L25'	804 POUND
L8	805 POUND	L21'	804 POUND
L12	805 POUND	L12'	804 POUND
L25	805 POUND	L8'	804 POUND
TOTAL= 3220 POUND		L4'	804 POUND
		E. ABUT.	810 POUND
		TOTAL= 4830 POUND	

CONCRETE SUPERSTRUCTURE= 56.5 CUYD			
PEORIA COUNTY		TAZEWELL COUNTY	
L4	5.65 CUYD	L25'	5.75 CUYD
L8	5.65 CUYD	L21'	5.60 CUYD
L12	5.65 CUYD	L12'	5.75 CUYD
L25	5.65 CUYD	L8'	5.75 CUYD
TOTAL= 22.6 CUYD		L4'	5.75 CUYD
		E. ABUT.	5.3 CUYD
		TOTAL= 33.9 CUYD	

BAR SPLICERS= 156 EACH			
PEORIA COUNTY		TAZEWELL COUNTY	
L4	16 EACH	L25'	16 EACH
L8	16 EACH	L21'	16 EACH
L12	16 EACH	L12'	16 EACH
L25	16 EACH	L8'	16 EACH
TOTAL= 62 EACH		L4'	16 EACH
		E. ABUT.	12 EACH
		TOTAL= 94 EACH	

PROTECTIVE COAT= 200 SQYD			
PEORIA COUNTY		TAZEWELL COUNTY	
L4	20.5 EACH	L25'	20.9 EACH
L8	20.5 EACH	L21'	20.9 EACH
L12	20.5 EACH	L12'	20.9 EACH
L25	20.5 EACH	L8'	20.9 EACH
TOTAL= 80 EACH		L4'	20.9 EACH
		E. ABUT.	15.7 EACH
		TOTAL= 120 EACH	

PREFORMED JOINT STRIP SEAL= 408 FOOT			
PEORIA COUNTY		TAZEWELL COUNTY	
L4	40.8 FOOT	L25'	40.8 FOOT
L8	40.8 FOOT	L21'	40.8 FOOT
L12	40.8 FOOT	L12'	40.8 FOOT
L25	40.8 FOOT	L8'	40.8 FOOT
TOTAL=163 FOOT		L4'	40.8 FOOT
		E. ABUT.	40.8 FOOT
		TOTAL= 245 FOOT	

TEMPORARY CONCRETE BARRIER= 3440 FOOT			
PEORIA COUNTY 1376		TAZEWELL COUNTY 2064	

RELOCATE TEMPORARY CONCRETE BARRIER=3440 FOOT			
PEORIA COUNTY 1376		TAZEWELL COUNTY 2064	

WIDE LOAD SIGNING=1.0 LSUM			
TAZEWELL COUNTY 1.0			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 VERT. SCALE, HORIZ. DATE 07-08-2006
 DRAWN BY CEJ
 CHECKED BY