

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	.	VERMILION	62	4

• (47Z-3)RS-1 & (52CS,4BZ-1)RS-3

SUMMARY OF QUANTITIES

URBAN
 STA. 96+60 to 183+00
 80% FED.
 20% STATE
 CONSTRUCTION CODE: 1000-2A

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,783.0
40600300	AGGREGATE (PRIME COAT)	TON	196.0
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	5.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	378.0
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8,805.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	157.0
40800030	AGGREGATE (PRIME COAT)	TON	3.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	132.0
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	97,823.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	1,571.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	19.0
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	127.0
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	17.0
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	200.0
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	134.0
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SQ YD	27.0
44201899	CLASS D PATCHES, TYPE II, 21 INCH	SQ YD	14.0
44201905	CLASS D PATCHES, TYPE IV, 21 INCH	SQ YD	107.0
60255500	MANHOLES TO BE ADJUSTED	EACH	23.0
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	6.0
60261325	INLETS TO BE ADJUSTED WITH NEW TYPE 11 GRATE	EACH	1.0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	19.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0

*SPECIALTY ITEMS