

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
820	*	DOUGLAS	57	19

*(37,37-1,2&3)RS-1

SHEET 1 OF 4

SCHEDULE OF QUANTITIES

TABULATION OF PARTIAL DEPTH PATCHES

SOUTHBOUND				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
STATION	LANE	LENGTH (FT)	WIDTH (FT)			
COLES - DOUGLAS COUNTY LINE						
130+44	SB	6.00	12.00	4.00	8.00	3.14
143+52	SB	4.00	12.00	4.00	5.33	2.09
149+54	SB	4.00	12.00	4.00	5.33	2.09
159+60	SB	6.00	12.00	4.00	8.00	3.14
167+71	SB	4.00	12.00	4.00	5.33	2.09
177+13	SB	6.00	6.00	4.00	4.00	1.57
177+36	SB	6.00	6.00	4.00	4.00	1.57
177+82	SB	10.00	12.00	4.00	13.33	5.23
178+43	SB	6.00	6.00	4.00	4.00	1.57
179+12	SB	6.00	20.00	4.00	13.33	5.23
191+73	SB	6.00	12.00	4.00	8.00	3.14
203+00	SB	6.00	6.00	4.00	4.00	1.57
SOUTHBOUND PAGE TOTALS					82.67	32.41

NORTHBOUND				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
STATION	LANE	LENGTH (FT)	WIDTH (FT)			
COLES - DOUGLAS COUNTY LINE						
130+44	NB	6.00	12.00	4.00	8.00	3.14
143+52	NB	4.00	12.00	4.00	5.33	2.09
149+54	NB	4.00	12.00	4.00	5.33	2.09
158+55	NB	6.00	12.00	4.00	8.00	3.14
168+70	NB	6.00	12.00	4.00	8.00	3.14
177+04	NB	4.00	6.00	4.00	2.67	1.05
177+73	NB	6.00	6.00	4.00	4.00	1.57
178+43	NB	6.00	6.00	4.00	4.00	1.57
179+34	NB	6.00	8.00	4.00	5.33	2.09
185+92	NB	6.00	20.00	4.00	13.33	5.23
NORTHBOUND PAGE TOTALS					64.00	25.09

PLOT DATE = 3/26/2007
 FILE NAME = c:\projects\4507002 (v.8)\7002text.dgn
 PLOT SCALE = 105.8824 / IN.
 USER NAME = philips,jr