

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
820	*	DOUGLAS	57	21

*(37,37-1,2&3)RS-1

SHEET 3 OF 4

SCHEDULE OF QUANTITIES

TABULATION OF PARTIAL DEPTH PATCHES

SOUTHBOUND				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
STATION	LANE	LENGTH (FT)	WIDTH (FT)			
149+53	SB	6.00	6.00	4.00	4.00	1.57
153+54	SB	6.00	12.00	4.00	8.00	3.14
194+66	SB	6.00	12.00	4.00	8.00	3.14
197+67	SB	6.00	12.00	4.00	8.00	3.14
STA. EQN. 210+85.93 (BK) - 501+01.77 (AH)						
517+77	SB	4.00	12.00	4.00	5.33	2.09
555+93	SB	6.00	12.00	4.00	8.00	3.14
SOUTHBOUND SHEET TOTALS					41.33	16.20

NORTHBOUND				EXISTING OVERLAY DEPTH (IN)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
STATION	LANE	LENGTH (FT)	WIDTH (FT)			
142+22	NB	6.00	12.00	4.00	8.00	3.14
146+45	NB	8.00	12.00	4.00	10.67	4.18
146+84	NB	8.00	12.00	4.00	10.67	4.18
149+53	NB	6.00	6.00	4.00	4.00	1.57
153+54	NB	6.00	12.00	4.00	8.00	3.14
158+68	NB	10.00	12.00	4.00	13.33	5.23
194+66	NB	6.00	12.00	4.00	8.00	3.14
197+67	NB	6.00	12.00	4.00	8.00	3.14
STA. EQN. 210+85.93 (BK) - 501+01.77 (AH)						
517+77	NB	4.00	12.00	4.00	5.33	2.09
555+93	NB	6.00	12.00	4.00	8.00	3.14
NORTHBOUND SHEET TOTALS					84.00	32.93

PLOT DATE = 3/26/2007
FILE NAME = c:\projects\4507002\70276\7002text.dgn
PLOT SCALE = 105,8824 / IN.
USER NAME = philipsjr

(CONTINUED NEXT SHEET)