

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
518	(380)RS	CHAMPAIGN	38	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

**80% FED.  
20% STATE**

**LOCATION OF WORK:**

FAS 518 (CH 22) FAS 518 (CH 22)  
 CHAMPAIGN CHAMPAIGN  
 COUNTY COUNTY  
 SN 010-0095  
 STA. 100+40.00  
 TO STA 236+26.00  
 STA. 308+59.63  
 RURAL RURAL  
 100% STATE 100% STATE  
 I000 X020-2A

**CONSTRUCTION TYPE CODE:**

CODE NO	ITEM	UNIT	TOTAL QUANTITY		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	525.0	525.0	0.0
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	139.0	139.0	0.0
35600700	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	SQ YD	3,525.0	3,525.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10,326.0	10,326.0	0.0
40600300	AGGREGATE (PRIME COAT)	TON	194.0	194.0	0.0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3,509.0	3,509.0	0.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	2.0	0.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	429.0	429.0	0.0
40600990	TEMPORARY RAMP	SQ YD	43.0	43.0	0.0
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	5,333.0	5,326.0	7.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	156.0	156.0	0.0
40800030	AGGREGATE (PRIME COAT)	TON	3.0	3.0	0.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	232.0	232.0	0.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	1,680.0	1,680.0	0.0
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	74.0	0.0	74.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,924.0	3,924.0	0.0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	100.0	0.0	100.0
67100100	MOBILIZATION	L SUM	1.0	1.0	0.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE

PLOT DATE = 3/22/2007  
 FILE NAME = s:\projects\100587\100587.dwg  
 USER NAME = ashley