

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
518	(380)RS	CHAMPAIGN	38	17
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

CLASS D PATCHING

STATION	DIRECTION	LANE	LENGTH	WIDTH	DEPTH	PATCH AREA			
						TYPE I 9.5'' (sq. yd)	TYPE II 9.5'' (sq. yd)	TYPE III 9.5'' (sq. yd)	TYPE IV 9.5'' (sq. yd)
121+28.00	NORTHBOUND	DL	25	6	9.5	0.0	0.0	16.7	0.0
119+88.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
119+88.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
119+64.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
119+64.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
119+35.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
119+35.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
118+55.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
118+55.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
117+80.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
117+80.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
116+07.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
116+07.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
111+18.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
111+18.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
110+35.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
110+35.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
109+88.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
109+88.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
108+45.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
108+45.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
107+15.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
107+15.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
105+88.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
105+88.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
105+27.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
104+46.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
102+94.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
102+94.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
100+32.00	SOUTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
100+32.00	NORTHBOUND	DL	4	11	9.5	4.9	0.0	0.0	0.0
SUB TOTALS						146.7	0.0	16.7	0.0
						(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)
TOTALS						229.8	44.1	113.3	133.3
						(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)
FINAL TOTALS						230.0	44.0	114.0	134.0
						(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DRAWN BY _____
CHECKED BY _____

PLOT DATE = 3/22/2007
FILE NAME = c:\projects\4598506 (v8)\ten.tdgn
PLOT SCALE = 42,352' / IN.
USER NAME = stults,j