

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
518	(380)RS	CHAMPAIGN	38	18
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

## PARTIAL DEPTH PATCHING

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	EXISTING OVERLAY THICKNESS (4 3/4" or less) (Inch)	PARTIAL DEPTH REMOVAL X4401705 (sq. yd)	PARTIAL DEPTH PATCHING X4421000 (tons)
183+88.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
184+22.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
184+22.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
184+90.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
184+91.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
185+51.00	SOUTHBOUND	DL	20	10	4.25	22.2	9.0
185+51.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
186+18.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
186+18.00	NORTHBOUND	DL	6	10	3.75	6.7	2.5
186+93.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
186+93.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
189+59.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
190+03.00	SOUTHBOUND	DL	10	10	4.25	11.1	4.5
191+01.00	SOUTHBOUND	DL	8	10	4.25	8.9	3.6
191+31.00	SOUTHBOUND	DL	6	6	4.25	4.0	1.6
191+60.00	SOUTHBOUND	DL	15	10	4.25	16.7	6.8
192+11.00	SOUTHBOUND	DL	10	6	4.25	6.7	2.7
194+87.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
197+56.00	SOUTHBOUND	DL	8	10	4.25	8.9	3.6
200+83.00	SOUTHBOUND	DL	10	10	4.25	11.1	4.5
202+71.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
202+71.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
203+48.00	SOUTHBOUND	DL	8	10	4.25	8.9	3.6
203+93.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
204+35.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
209+28.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
212+96.00	SOUTHBOUND	DL	6	10	4.25	6.7	2.7
217+94.00	SOUTHBOUND	DL	8	10	4.25	8.9	3.6
229+64.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
229+64.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
SUB TOTALS						200.7 (sq. yd)	80.2 (Tons)

PLOT DATE : 3/22/2007  
 FILE NAME : c:\projects\4598586 (v8)\test.dgn  
 PLOT SCALE : 42.3525' / IN.  
 USER NAME : stults,j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_