

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
518	(380)RS	CHAMPAIGN	38	19
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

## PARTIAL DEPTH PATCHING

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	EXISTING OVERLAY THICKNESS (4 3/4" or less) (Inch)	PARTIAL DEPTH REMOVAL X4401705 (sq. yd)	PARTIAL DEPTH PATCHING X4421000 (tons)
230+19.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
230+19.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
230+88.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
230+88.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
230+99.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
230+99.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
232+08.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
232+08.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
233+15.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
233+15.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
234+33.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
234+33.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
235+11.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
235+11.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
235+81.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
235+81.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
235+97.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
235+97.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
236+89.00	SOUTHBOUND	DL	25	10	3.75	27.8	10.5
236+89.00	NORTHBOUND	DL	25	10	3.75	27.8	10.5
237+07.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
237+07.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
238+26.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
238+26.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
242+85.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
242+85.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
243+61.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
243+61.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
244+65.00	SOUTHBOUND	DL	8	10	3.75	8.9	3.4
244+65.00	NORTHBOUND	DL	8	10	3.75	8.9	3.4
SUB TOTALS						188.9 (sq. yd)	71.4 (tons)

PLOT DATE = 3/22/2007  
 FILE NAME = c:\projects\4598586 (v8)\test.dgn  
 PLOT SCALE = 42,352" / IN.  
 USER NAME = stults,j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_