

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
518	(380)RS	CHAMPAIGN	38	20
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

PARTIAL DEPTH PATCHING

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	EXISTING OVERLAY THICKNESS (4 3/4" or less) (Inch)	PARTIAL DEPTH REMOVAL X4401705 (sq. yd)	PARTIAL DEPTH PATCHING X4421000 (tons)
245+78.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
245+78.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
247+05.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
247+05.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
247+96.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
247+96.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
248+67.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
248+67.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
248+85.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
248+85.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
249+04.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
249+04.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
349+53.00	NORTHBOUND	DL	12	6	3.75	8.0	3.0
252+49.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
252+91.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
253+61.00	NORTHBOUND	DL	15	10	3.75	16.7	6.3
254+56.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
254+81.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
257+28.00	SOUTHBOUND	DL	8	10	4.25	8.9	3.6
261+46.00	SOUTHBOUND	DL	4	10	4.25	4.4	1.8
262+67.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
263+11.00	NORTHBOUND	DL	20	6	3.75	13.3	5.0
264+02.00	SOUTHBOUND	DL	8	10	4.25	8.9	3.6
264+02.00	NORTHBOUND	DL	8	10	3.75	8.9	3.4
265+25.00	NORTHBOUND	DL	6	10	3.75	6.7	2.5
266+89.00	SOUTHBOUND	DL	6	10	4.25	6.7	2.7
268+22.00	SOUTHBOUND	DL	12	10	3.75	13.3	5.0
271+74.00	SOUTHBOUND	DL	10	10	4.25	11.1	4.5
271+74.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
272+15.00	SOUTHBOUND	DL	15	6	4.25	10.0	4.1
SUB TOTALS						196.9 (sq. yd)	76.3 (tons)

PLOT DATE = 3/22/2007
 FILE NAME = c:\projects\4598586 (v8)\ten.tdgn
 PLOT SCALE = 42.3525' / IN.
 USER NAME = stults,j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DRAWN BY _____
 CHECKED BY _____