

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
518	(380)RS	CHAMPAIGN	38	21
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

PARTIAL DEPTH PATCHING

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	EXISTING OVERLAY THICKNESS (4 3/4" or less) (Inch)	PARTIAL DEPTH REMOVAL X4401705 (sq. yd)	PARTIAL DEPTH PATCHING X4421000 (tons)
274+08.00	SOUTHBOUND	DL	5	10	4.25	5.6	2.3
275+13.00	SOUTHBOUND	DL	6	10	4.25	6.7	2.7
276+11.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
276+11.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
282+13.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
282+13.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
282+52.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
283+00.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
283+00.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
283+68.00	SOUTHBOUND	DL	12	10	3.75	13.3	5.0
283+68.00	NORTHBOUND	DL	12	10	3.75	13.3	5.0
284+82.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
284+82.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
287+99.00	SOUTHBOUND	DL	4	10	3.75	4.4	1.7
287+99.00	NORTHBOUND	DL	4	10	3.75	4.4	1.7
292+40.00	SOUTHBOUND	DL	4	11	3.75	4.9	1.8
292+40.00	NORTHBOUND	DL	4	11	3.75	4.9	1.8
293+23.00	SOUTHBOUND	DL	6	11	3.75	7.3	2.8
293+23.00	NORTHBOUND	DL	6	11	3.75	7.3	2.8
293+56.00	SOUTHBOUND	DL	4	11	3.75	4.9	1.8
293+56.00	NORTHBOUND	DL	4	11	3.75	4.9	1.8
293+68.00	SOUTHBOUND	DL	4	11	3.75	4.9	1.8
293+68.00	NORTHBOUND	DL	4	11	3.75	4.9	1.8
293+84.00	SOUTHBOUND	DL	4	11	3.75	4.9	1.8
293+84.00	NORTHBOUND	DL	4	11	3.75	4.9	1.8
294+26.00	SOUTHBOUND	DL	4	11	3.75	4.9	1.8
294+26.00	NORTHBOUND	DL	4	11	3.75	4.9	1.8
294+90.00	CENTERLINE	DL	10	4	3.75	4.4	1.7
295+03.00	SOUTHBOUND	DL	4	11	3.75	4.9	1.8
295+03.00	NORTHBOUND	DL	4	11	3.75	4.9	1.8
SUB TOTALS						165.6 (sq. yd)	62.9 (tons)

PLOT DATE = 3/22/2007
 FILE NAME = c:\projects\4598586 (v8)\ten.tdgn
 PLOT SCALE = 42.3525' / IN.
 USER NAME = stults,j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DRAWN BY _____
 CHECKED BY _____