

GUARDRAIL SCHEDULES

SHEET 2 of 19

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	.	..	153	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

- D5 SAFETY IMPROVEMENT 2007-2
- CHAMPAIGN, COLES, & DOUGLAS

DOUGLAS COUNTY: RURAL

015-0063

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION		LENGTH (FT)
1385+98.00		1387+50.00	LT	152.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION		EACH
1389+03.65		1389+53.65	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)
1386+41.15		1389+03.65	LT	262.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION		EACH
1385+84.50		1386+41.15	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
1389+53.65	LT	1.0

021-2000

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION		LENGTH (FT)
1394+92.00		1396+54.50	RT	162.50
1397+34.00		1398+96.50	LT	162.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION		EACH
1393+61.20		1394+11.20	RT	1.0
1399+64.80		1400+14.80	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)
1394+11.20		1396+11.20	RT	200.00
1397+64.80		1399+64.80	LT	200.00

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION	TO	STATION		LENGTH (FT)
1396+11.20		1396+36.20	RT	25.00
1397+39.80		1397+64.80	LT	25.00

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION	TO	STATION		LENGTH (FT)
1396+36.20		1396+61.20	RT	25.00
1397+14.80		1397+39.80	LT	25.00

021-2000, Con't,

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION		EACH
1396+61.20		1396+75.47	RT	1.0
1397+00.53		1397+14.80	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
1393+61.20	RT	1.0
1400+14.80	LT	1.0

021-0024

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION		LENGTH (FT)
1491+19.00		1492+94.00	RT	175.00
1492+59.00		1494+34.00	LT	175.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION		EACH
1489+88.88		1490+38.88	RT	1.0
1495+14.18		1495+64.18	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)
1490+38.88		1492+26.38	RT	187.50
1493+26.68		1495+14.18	LT	187.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION		EACH
1492+26.38		1492+83.03		1.0
1492+69.63		1493+26.28		1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
1489+88.88	RT	1.0
1495+64.18	LT	1.0

021-0024 (RAMPS)

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

STATION	TO	STATION		EACH	
124+48.23		124+98.23	RT	1.0	(RAMP A)
58+01.77		57+51.77 (IL 133)	RT	1.0	(RAMP B)
56+23.23		56+73.23 (IL 133)	LT	1.0	(RAMP B)
390+75.00		391+25.00	RT	1.0	(RAMP C)
57+50.00		58+00.00 (IL 133)	RT	1.0	(RAMP C)

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)	
124+98.23		127+35.73	RT	237.50	(RAMP A)
230+98.23		236+60.73	RT	562.50	(RAMP B)
231+10.63		231+60.63	LT	50.00	(RAMP B)
391+25.00		394+50.00	RT	325.00	(RAMP C)

021-0024 (RAMPS), Con't,

#5000828 RADIUS GUARDRAIL

STATION	TO	STATION		LENGTH (FT)	
(IL 133) 57+51.77		230+98.23	RT	87.50	(RAMP B)
(IL 133) 56+73.23		231+60.63	LT	50.00	(RAMP B)
394+50.00		57+50.00 (IL 133)	RT	87.50	(RAMP C)

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION		EACH	
127+35.73		127+50.00	RT	1.0	(RAMP A)
236+60.73		236+75.00	RT	1.0	(RAMP B)
231+60.73		231+75.00	LT	1.0	(RAMP B)

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
124+48.23	RT	1.0
58+01.77 (IL 133)	RT	1.0
56+73.23 (IL 133)	LT	1.0
390+75.00	RT	1.0
57+50.00 (IL 133)	RT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\p\projects\d51406\148\70628\sheet2.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 2 of 19

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 03/23/07 CHECKED BY: M.L.B.