

GUARDRAIL SCHEDULES

SHEET 3 of 19

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	••	153	16

STA. TO STA.
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
 • D5 SAFETY IMPROVEMENT 2007-2
 •• CHAMPAIGN, COLES, & DOUGLAS

021-0001 & 021-0002

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
1508+45.00	125+31.40	RT	962.50
123+56.40	125+31.40	MED RT	175.00
126+97.10	138+59.60	RT	1162.50
1508+45.00	125+31.40	LT	962.50
126+97.10	128+72.10	MED LT	175.00
126+97.10	139+34.60	LT	1237.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
117+23.25	117+73.25	RT	1.0
121+98.25	122+48.25	MED RT	1.0
129+80.25	130+30.25	MED LT	1.0
140+30.25	140+80.25	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
117+73.25	124+85.75	RT	712.50
122+48.25	124+85.75	MED RT	237.50
127+42.75	137+92.75	RT	1050.00
120+10.75	124+85.75	LT	475.00
127+42.75	129+80.25	MED LT	237.50
127+42.75	140+30.25	LT	1287.50

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION TO	STATION		EACH
124+85.75	125+31.40	RT	1.0
124+85.75	125+31.40	MED RT	1.0
126+97.10	127+42.75	RT	1.0
124+85.75	125+31.40	LT	1.0
126+97.10	127+42.75	MED LT	1.0
126+97.10	127+42.75	LT	1.0

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
137+92.75	138+07.02	RT	1.0
119+96.48	120+10.75	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
117+23.25	RT	1.0
122+10.75	MED RT	1.0
130+30.25	MED LT	1.0
140+80.25	LT	1.0

021-0041

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
150+57.90	152+07.90	RT	150.00
151+92.00	153+42.00	LT	150.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
149+12.35	149+62.35	RT	1.0
154+37.65	154+87.65	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
149+62.35	151+49.85	RT	187.50
152+50.15	154+37.65	LT	187.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
151+49.85	152+06.50		1.0
151+93.50	152+50.15		1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
149+12.35	RT	1.0
154+87.65	LT	1.0

021-8300

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
250+22.50	253+35.00	RT	312.50
252+65.00	255+77.50	LT	312.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
250+18.75	250+68.75	RT	1.0
255+31.25	255+81.25	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
250+68.75	252+68.75	RT	200.00
253+31.25	255+31.25	LT	200.00

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION TO	STATION		LENGTH (FT)
252+68.75	252+93.75	RT	25.00
253+06.25	253+31.25	LT	25.00

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION TO	STATION		LENGTH (FT)
252+93.75	253+06.25	RT	12.50
252+93.75	253+06.25	LT	12.50

021-8300, Con't.

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
253+06.25	253+20.52	RT	1.0
252+79.48	252+93.75	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
250+18.75	RT	1.0
255+81.25	LT	1.0

021-0037

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
308+46.10	311+58.60	RT	312.50
311+45.40	314+57.90	LT	312.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
308+62.40	309+12.40	RT	1.0
313+89.70	314+39.70	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
309+12.40	310+99.90	RT	187.50
312+02.20	313+89.70	LT	187.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
310+99.90	311+56.55	RT	1.0
311+45.55	312+02.20	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
308+62.40	RT	1.0
314+39.70	LT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\projects\rs\d514406\1\8\70628\sheet3.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pfer-sonbr