

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	••	153	22
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D5 SAFETY IMPROVEMENT 2007-2 •• CHAMPAIGN, COLES, & DOUGLAS				

010-0128

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
133+32.37		136+65.52	333.15	RT
136+50.48		139+75.48	325.00	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
139+21.13		139+71.13	1.0	LT

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

133+32.37		133+82.37	1.0	RT
-----------	--	-----------	-----	----

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)	
133+82.37		136+07.37	225.00	RT
137+08.63		139+21.13	212.50	LT

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH	
136+07.37		136+64.02	1.0	RT
136+51.98		137+08.63	1.0	LT

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	
139+71.13	1.0	LT
133+32.37	1.0	RT

010-8016

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
187+16.25		190+67.00	331.77	RT
190+13.00		193+44.77	331.77	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
187+33.75		187+83.75	1.0	RT
192+96.25		193+46.25	1.0	LT

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)	
187+83.75		190+08.75	225.00	RT
190+71.25		192+96.25	225.00	LT

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION	TO	STATION	LENGTH (FT)	
190+08.75		190+33.75	25.00	LT
190+46.25		190+71.25	25.00	LT

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION	TO	STATION	LENGTH (FT)	
190+33.75		190+46.25	12.50	RT
190+33.75		190+46.25	12.50	LT

010-8016, Con't.

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH	
190+46.25		190+60.52	1.0	RT
190+19.48		190+33.75	1.0	LT

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	
187+33.75	1.0	RT
193+46.25	1.0	LT

CHAMPAIGN COUNTY: URBAN

010-0105

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
240+93.87		244+14.52	320.65	RT
243+97.48		247+18.13	320.65	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
240+93.87		241+43.87	1.0	RT
246+68.13		247+18.13	1.0	LT

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)	
241+43.87		243+56.37	212.50	RT
244+55.63		246+68.13	212.50	LT

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH	
243+56.37		244+13.02	1.0	RT
243+98.98		244+55.63	1.0	LT

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	EACH	
240+93.87	1.0	RT
247+18.13	1.0	LT

010-0176

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)	
347+06.37		350+39.52	333.15	RT
350+30.38		353+63.53	333.15	LT

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH	
347+06.37		347+56.37	1.0	RT
353+13.53		353+63.53	1.0	LT

PLOT DATE = 3/30/2007
 FILE NAME = c:\p\projects\d514406\108\70628\sheet9.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 9 of 19
 SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 03/23/07 CHECKED BY: M.L.B.