

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	••	153	23
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D5 SAFETY IMPROVEMENT 2007-2				
•• CHAMPAIGN, COLES, & DOUGLAS				

010-0005 & 010-0006

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
359+53.52	362+16.02	RT	262.50
359+26.32	362+01.32	MED RT	300.00
362+77.98	365+52.98	LT	275.00
362+92.68	366+05.18	MED LT	312.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
359+07.87	359+57.87	RT	1.0
357+93.17	358+43.17	MED RT	1.0
365+36.13	365+86.13	LT	1.0
366+50.83	367+00.83	MED LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
359+57.87	361+70.37	RT	212.50
358+43.17	361+55.67	MED RT	312.50
363+23.63	365+36.13	LT	212.50
363+38.33	366+50.83	MED LT	312.50

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION TO	STATION		EACH
361+70.37	362+16.02	RT	1.0
361+55.67	362+01.32	MED RT	1.0
362+77.98	363+23.63	LT	1.0
362+92.68	363+38.33	MED LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
359+07.87	RT	1.0
357+93.17	MED RT	1.0
365+86.13	LT	1.0
367+00.83	MED LT	1.0

010-0007/0008 & 010-0103

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
396+82.33	399+94.83	RT	312.50
400+96.99	403+38.75	RT	241.76 (attaches 0008 of 0103)
396+89.25	399+89.25	MED RT	300.00
400+88.50	403+23.42	MED RT	234.92
400+53.79	406+28.79	MED LT	575.00
400+45.30	407+57.80	LT	712.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
396+74.18	397+24.18	RT	1.0
397+10.48	397+60.48	MED RT	1.0
406+24.90	406+74.90	LT	1.0
405+86.94	406+36.94	MED LT	1.0

010-0007/0008 & 010-0103, Con't.

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
397+24.18	399+49.18	RT	225.00
397+60.48	399+47.98	MED RT	187.50
401+42.64	402+82.10	RT	139.46
401+34.15	403+09.15	MED RT	175.00
400+90.95	403+00.10	LT	209.15
403+99.90	406+24.90	LT	225.00
400+99.44	405+86.94	MED LT	487.50

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION TO	STATION		EACH
399+49.18	399+94.83	RT	1.0
399+47.98	399+93.63	MED RT	1.0
400+96.99	401+42.64	RT	1.0
400+88.50	401+34.15	MED RT	1.0
400+45.30	400+90.95	LT	1.0
400+53.79	400+99.44	MED LT	1.0

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
402+82.10	403+38.75	RT	1.0

63100127 TRAFFIC BARRIER TERMINAL TYPE 6B (SPECIAL)

STATION TO	STATION		EACH
403+00.10	403+43.85	LT	1.0
403+56.15	403+99.90	LT	1.0

Z0026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION TO	STATION		LENGTH (FT)
403+43.85	403+56.15	LT	12.3

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
403+09.15	403+23.42	MED RT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
396+74.18	RT	1.0
397+10.48	MED RT	1.0
406+65.95	LT	1.0
406+36.94	MED LT	1.0

SIGN FOUNDATION @ 414+69.00

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
411+94.40	414+46.17	RT	251.77

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
411+94.40	412+44.40	RT	1.0

SIGN FOUNDATION @ 414+69.00, Con't.

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
412+44.40	414+31.90	RT	187.50

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
414+31.90	414+46.17	RT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
411+94.40	RT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\p\projects\d514406\108\70628\sheet10.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 10 of 19
 SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 03/23/07 CHECKED BY: M.L.B.