

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	.	..	153	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* D5 SAFETY IMPROVEMENT 2007-2 ** CHAMPAIGN, COLES, & DOUGLAS				

010-0009 & 010-0010

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
440+70.50	454+22.65	RT	1352.15
451+53.01	454+23.65	MED RT	270.64
457+20.85	465+63.97	RT	843.12
443+83.23	454+26.45	LT	1043.22
457+24.35	459+94.99	MED LT	270.64
457+25.34	466+14.00	LT	888.66

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

STATION TO	STATION		EACH
440+64.50	441+14.50	RT	1.0

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
451+53.00	452+03.00	MED RT	1.0
465+70.99	466+20.99	LT	1.0
459+45.00	459+90.65	MED LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
441+14.50	453+77.00	RT	1262.50
452+03.00	453+78.00	MED RT	175.00
457+66.50	465+54.00	RT	787.50
443+93.30	453+80.80	LT	987.50
457+70.00	459+45.00	MED LT	175.00
457+70.99	465+70.99	LT	800.00

63100085 TRAFFIC BARRIER TERMINAL TYPE 6

STATION TO	STATION		EACH
453+77.00	454+22.65	RT	1.0
453+78.00	454+23.65	MED RT	1.0
457+20.85	457+66.50	RT	1.0
453+80.80	454+26.45	LT	1.0
457+24.35	457+70.00	MED LT	1.0
457+25.34	457+70.99	LT	1.0

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
443+79.03	443+93.30	LT	1.0
465+54.00	465+68.27	RT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
440+64.50	RT	1.0
451+53.00	MED RT	1.0
466+20.99	LT	1.0
459+90.65	MED LT	1.0

SIGN FOUNDATION @ 466+00.00

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
463+12.20	465+63.97	MED RT	251.77

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
463+12.20	463+62.20	MED RT	1.0
468+37.53	468+87.53	MED LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
463+62.20	465+49.70	MED RT	187.50
466+50.03	468+37.53	MED LT	187.50

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
465+49.70	465+63.97	MED RT	1.0
466+35.76	466+50.03	MED LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
463+12.20	MED RT	1.0
468+87.53	MED LT	1.0

010-0034 & 010-0035

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
478+24.61	481+84.98	RT	360.37
480+98.98	481+84.98	MED RT	86.00
480+98.98	484+71.68	LT	372.70
480+98.98	481+84.98	MED LT	86.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
478+13.58	478+63.58	RT	1.0
484+32.88	484+82.88	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
478+63.58	480+38.58	RT	175.00
482+45.38	484+32.88	LT	187.50

Z0026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION TO	STATION		LENGTH (FT)
480+95.23	481+95.23	RT	100.00
480+76.23	481+88.73	LT	112.50
480+98.98	481+86.48	MED RT	87.50
480+98.98	481+86.48	MED LT	87.50

010-0034 & 010-0035, Con't.

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
480+38.58	480+95.23	RT	1.0
481+88.73	482+45.38	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
478+13.58	RT	1.0
484+82.88	LT	1.0

SIGN FOUNDATION @ 496+05.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
493+90.73	494+40.73	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
494+40.73	495+90.73	LT	150.00

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
495+90.73	496+05.00	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
494+40.73	LT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\projects\010-0034\010-0035\010-0035.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr