

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	••	153	25
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D5 SAFETY IMPROVEMENT 2007-2 •• CHAMPAIGN, COLES, & DOUGLAS				

010-0215

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
496+75.00	499+89.27	RT	314.27
500+85.73	504+00.00	LT	314.27

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
503+50.00	504+00.00	LT	1.0

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

STATION TO	STATION		LENGTH (FT)
496+75.00	497+25.00	RT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
497+25.00	499+75.00	RT	250.00
501+00.00	503+50.00	LT	250.00

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
499+75.00	499+89.27	RT	1.0
500+85.73	501+00.00	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
504+00.00	LT	1.0
497+25.00	RT	1.0

010-0174

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
506+94.37	509+93.63	RT	299.26
509+47.98	512.68.63	LT	320.65

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
506+86.98	507+36.98	RT	1.0
512+29.63	512+79.63	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
507+36.98	509+36.98	RT	200.00
510+04.63	512+29.63	LT	225.00

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
509+36.98	509+93.63	RT	1.0
509+47.98	510+04.63	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
506+86.98	RT	1.0
512+79.63	LT	1.0

SIGN FOUNDATION @ 529+00.00

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
526+25.40	528+77.17	RT	251.77

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
526+25.40	526+75.40	RT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
526+75.40	528+62.90	RT	187.50

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
528+62.90	528+77.17	RT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
526+25.40	RT	1.0

SIGN FOUNDATION @ 547+00.00

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
547+04.93	549+55.60	RT	250.67

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
543+98.23	544+48.23	RT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
544+48.23	546+85.73	RT	237.50

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
546+85.73	547+00.00	RT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
543+98.23	RT	1.0

010-0011

63200310 GUARDRAIL REMOVAL

STATION TO	STATION		LENGTH (FT)
564+29.60	566+93.69	RT	264.09
565+51.04	568+78.71	LT	327.67

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
562+83.95	563+33.95	RT	1.0
568+93.71	569+43.71	LT	1.0

010-0011, Con't.

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
563+33.95	566+33.95	RT	300.00
565+57.41	565+69.91	LT	12.50
566+81.21	568+93.71	LT	212.50

70026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION TO	STATION		LENGTH (FT)
566+13.66	566+37.46	LT	23.80

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
566+33.95	566+90.60	RT	1.0

63100127 TRAFFIC BARRIER TERMINAL TYPE 6B (SPECIAL)

STATION TO	STATION		EACH
565+69.91	566+13.66	LT	1.0
566+37.46	566+81.21	LT	1.0

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION TO	STATION		EACH
565+43.14	565+57.41	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
563+71.45	RT	1.0
569+43.71	LT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\p\projects\d514406\108\70628\sheet25.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 12 of 19
 SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 03/23/08 CHECKED BY: M.L.B.