

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	.	**	153	26
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D5 SAFETY IMPROVEMENT 2007-2 ** CHAMPAIGN, COLES, & DOUGLAS				

010-0050

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)
580+70.54		582+72.67	202.13
582+31.93		584+09.52	177.59

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
579+31.85		579+81.85	1.0
585+18.15		585+68.15	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)
579+81.85		581+94.35	212.50
583+05.65		585+18.15	212.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH
581+94.35		582+51.00	1.0
582+49.00		583+05.65	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	RT	EACH
579+31.85	RT	1.0
585+68.15	LT	1.0

010-0018 & 010-0019

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)
595+66.52		598+41.52	275.00
597+03.22		598+53.22	150.00
597+14.92		599+89.92	275.00
597+03.22		598+53.22	150.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
595+61.84		596+11.84	1.0
599+82.64		600+32.64	1.0

010-0018 & 010-0019, Con't,

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)
596+11.84		596+74.34	62.50
598+82.64		599+82.64	100.00

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH
596+74.34		597+30.99	1.0
598+25.99		598+82.64	1.0

Z0026260 * FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION	TO	STATION	LENGTH (FT)
597+30.99		598+05.99	75.00
597+50.99		598+25.99	75.00
597+47.24		598+09.74	62.50
597+47.24		598+09.74	62.50

SIGN FOUNDATION @ 610+92.90

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)
610+92.90		614+55.40	362.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
612+57.17		613+07.17	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)
611+07.17		612+57.17	150.00

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH
610+92.90		611+07.17	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	RT	EACH
613+07.17	RT	1.0

010-0100

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)
624+49.47		626+12.00	162.53
627+21.00		628+83.97	162.97

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
622+67.74		623+17.74	1.0
630+15.77		630+65.77	1.0

010-0100, Con't,

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)
623+17.74		625+30.24	212.50
628+03.27		630+15.77	212.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION	EACH
625+30.24		625+86.89	1.0
627+46.62		628+03.27	1.0

Z0026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION	TO	STATION	FOOT
625+86.89		626+14.89	28.0
627+18.62		627+46.62	28.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	RT	EACH
622+67.74	RT	1.0
630+65.77	LT	1.0

SIGN FOUNDATION @ 665+03.81

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION	LENGTH (FT)
664+66.41		667+28.91	262.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION	EACH
667+72.96		668+22.96	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	LENGTH (FT)
665+60.46		667+72.96	212.50

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION	EACH
665+03.81		665+60.46	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION	RT	EACH
668+22.96	LT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\projects\051406\108\70628\013sheets.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 13 of 19
 SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 03/23/07 CHECKED BY: M.L.B.