

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	.	..	153	27
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• D5 SAFETY IMPROVEMENT 2007-2 .. CHAMPAIGN, COLES, & DOUGLAS				

CHAMPAIGN COUNTY: RURAL

010-0185, Con't,

010-0172/010-0201, Con't,

010-0171

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION		LENGTH (FT)
706+67.16		708+54.66	RT	187.50
708+75.00		710+62.50	LT	187.50

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION		EACH
705+49.01		705+99.01	RT	1.0
711+30.65		711+80.65	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)
705+99.01		708+11.51	RT	212.50
709+18.15		711+30.65	LT	212.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION		EACH
708+11.51		708+68.16	RT	1.0
708+61.50		709+18.15	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
705+49.01	RT	1.0
711+80.65	LT	1.0

010-0185

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION		LENGTH (FT)
763+64.50		765+64.50	RT	200.00
765+62.50		770+62.50	LT	500.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION		EACH
762+39.16		762+89.16	RT	1.0
771+63.74		772+13.74	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)
762+89.16		765+01.66	RT	212.50
766+26.24		771+63.74	LT	537.50

(GUARDRAIL RUNS ACROSS 010-2000)

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION		EACH
765+01.66		765+58.31	RT	1.0
765+69.59		766+26.24	LT	1.0

Z0026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION	TO	STATION		EACH
765+58.31		765+73.31	RT	15.0
765+54.59		765+69.59	LT	15.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
762+39.16	RT	1.0
772+13.74	LT	1.0

010-2000

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION		LENGTH (FT)
767+45.00		769+45.00	RT	200.00

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION		EACH
765+98.23		766+48.23	RT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)
766+48.23		768+85.73	RT	237.50

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION		EACH
768+85.73		769+00.00	RT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
766+48.23	RT	1.0

010-0172 / 010-2001

63200310 GUARDRAIL REMOVAL

STATION	TO	STATION		LENGTH (FT)
873+95.70		877+83.20	RT	387.50 (010-0201 north
876+71.25		879+46.25	LT	275.00 of 010-0172)

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION	TO	STATION		EACH
872+70.72		873+20.72	RT	1.0
880+33.40		880+83.40	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION		LENGTH (FT)
873+20.72		875+32.22	RT	212.50
876+53.52		877+14.75	RT	61.23
878+20.90		880+33.40	LT	212.50

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION	TO	STATION		LENGTH (FT)
877+14.75		877+39.75	RT	25.00

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION	TO	STATION		LENGTH (FT)
877+39.75		877+52.25	RT	12.50
877+01.02		877+13.52	LT	12.50

Z0026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION	TO	STATION		LENGTH (FT)
875+89.87		875+96.87	RT	7.0
877+57.25		877+64.25	LT	7.0

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION	TO	STATION		EACH
875+33.22		875+89.87	RT	1.0
875+96.87		876+53.52	RT	1.0
877+13.52		877+57.25	LT	1.0
877+64.25		878+20.90	LT	1.0

63100045 TRAFFIC BARRIER TERMINAL TYPE 2

STATION	TO	STATION		EACH
877+52.25		877+66.52	RT	1.0
876+86.85		877+01.02	LT	1.0

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
872+70.72	RT	1.0
880+83.40	LT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\p\projects\d514406\108\70628\sheet14.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 14 of 19

SCALE: NOT TO SCALE
 DATE: 03/23/07

DRAWN BY: B.B.P.
 CHECKED BY: M.L.B.