

GUARDRAIL SCHEDULES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	•	••	153	32
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- D5 SAFETY IMPROVEMENT 2007-2
- CHAMPAIGN, COLES, & DOUGLAS

010-8311 & 010-8312, Con't.

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
1584+43.08	RT	1.0
1583+43.08	MED RT	1.0
1591+49.82	MED L T	1.0

010-0082

63100169 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

STATION TO	STATION		EACH
1593+07.88	1593+57.88	LT	1.0

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION TO	STATION		LENGTH (FT)
1587+82.12	1590+45.60	RT	263.48
1587+82.12	1589+75.08	LT	192.96
1590+95.38	1593+07.88	LT	212.50

63100089 TRAFFIC BARRIER TERMINAL TYPE 6B

STATION TO	STATION		EACH
1590+45.60	1591+02.25	RT	1.0
1589+75.08	1590+31.73	LT	1.0
1590+38.73	1590+95.38	LT	1.0

Z0026260 FURNISHING AND INSTALLING TUBULAR THRIE BEAM

STATION TO	STATION		LENGTH (FT)
1590+31.73	1590+38.73	LT	7.0

63100070 TRAFFIC BARRIER TERMINAL TYPE 5

STATION TO	STATION		EACH	
1587+67.45	1587+82.12	RT	1.0	(attaches 8312 to 0082)
1587+67.45	1587+82.12	LT	1.0	(attaches 8311 to 0082)

78201000 TERMINAL MARKER - DIRECT APPLIED

STATION		EACH
1593+57.88	LT	1.0

PLOT DATE = 3/30/2007
 FILE NAME = c:\projects\d5\406\1\8\70628\allsheets.dgn
 PLOT SCALE = 42.3523 / IN.
 USER NAME = pier-sonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION
GUARDRAIL SCHEDULES
 F.A.I. ROUTE 57 (I-57)
 SECTION D5 SAFETY IMPROVEMENT 2007-2
 CHAMPAIGN, COLES, & DOUGLAS COUNTIES
 Page 19 of 19
 SCALE: NOT TO SCALE DRAWN BY: B.B.P.
 DATE: 03/23/07 CHECKED BY: M.L.B.