

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6401	(20,21)RS-3	MCLEAN	12	6

SUMMARY OF QUANTITIES

MANHOLES TO BE ADJUSTED

<u>STATION</u>	<u>OFFSET</u>	<u>QUANTITY</u>
0+412	10.6	1
0+751	1.8	1
<u>TOTAL = 2 *</u>		

* AS PER PLAN PREPARATION MEMORANDUM 60-11, ONE MANHOLE WILL BE USED TO ESTABLISH PAY QUANTITY.

PAVEMENT MARKING REMOVAL

<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>SO. FT.</u>
0+00		0+06	910.00
<u>TOTAL = 910 SO. FT.</u>			

REMOVAL AREA FOR CROSSWALK AT LOCUST ST.

VALVE BOXES TO BE ADJUSTED

<u>STATION</u>	<u>OFFSET</u>	<u>QUANTITY</u>
12+19.2	17.5' Lt.	1
12+20.9	13.1' Rt.	1
<u>TOTAL = 2</u>		

PAVEMENT MARKING

<u>US 150</u>		LETTERS	4"	4"	6"	12"	24"	RRPM
<u>STATION</u>	<u>TO</u>	<u>SYMBOLS</u>	<u>WHITE</u>	<u>YELLOW</u>	<u>WHITE</u>	<u>WHITE</u>	<u>WHITE</u>	<u>CRYSTAL</u>
		<u>(SQ FT)</u>	<u>(FOOT)</u>	<u>(FOOT)</u>	<u>(FOOT)</u>	<u>(FOOT)</u>	<u>(FOOT)</u>	<u>(EACH)</u>
0+00	12+27.5	63.0	267.0	1208.0	148.0	151.0	50.0	27.0
<u>TOTALS =</u>		<u>63.0</u>	<u>267.0</u>	<u>1208.0</u>	<u>148.0</u>	<u>151.0</u>	<u>50.0</u>	<u>27.0</u>

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

<u>US 150</u>		<u>STATION</u>	<u>TYPE</u>	<u>EACH</u>
0+00		12+27.5 27	CRYSTAL	10
0+00		12+27.5 27	AMBER	17
<u>TOTAL =</u>				<u>27</u>

TEMPORARY RAMP

<u>US 150</u>	<u>STATION</u>	<u>TO</u>	<u>STATION</u>	<u>SO YD</u>
	0+00		0+05	20.27
	12+22.50		12+27.50	21.66
<u>USE =</u>				<u>41.93</u>
<u>TOTAL =</u>				<u>42</u>