

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
730	62RS-2	McLEAN	17	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

MANHOLES TO BE ADJUSTED

STATION	OFFSET	QUANTITY
239+04.50	10' RT	1
244+01.00	17' RT	1
244+67.00	10.7' LT	1
247+29.00	10.3' RT	1
247+97.30	12.2' RT	1
248+27.00	9.7' LT	1
249+20.60	11.3' RT	1
251+19.00	11.9' RT	1

TOTAL = 8 • AS PER PLAN PREPARATION MEMORANDUM 60-11,
30% OF MANHOLES WILL BE USED TO ESTABLISH PAY QUANTITY.

VALVE BOXES TO BE ADJUSTED

STATION	OFFSET	QUANTITY
244+67.00	10.1' LT	1
247+73.10	14.5' RT	1
247+76.60	5.2' LT	1

TOTAL = 3

PAVEMENT MARKING

STATION	TO	STATION	LETTERS SYMBOLS (SQ. FT.)	4" WHITE (FOOT)	6" WHITE (FOOT)	12" WHITE (FOOT)	24" WHITE (FOOT)	RRPM CRYSTAL (EACH)
US 51	239+00	251+57	196.0	540.0	316.0	342.0	67.0	36.0
TOTALS =			196.0	569.0	316.0	342.0	67.0	36.0

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

STATION	TO	STATION	EACH
US 51	239+00	251+57	36
TOTAL =			36

TEMPORARY RAMP

STATION	TO	STATION	SQ. YD.
US 51	239+00	239+05	17
	251+52	251+57	17
TOTAL =			34

PLOT DATE = 3/27/2007
 FILE NAME = G:\projects\view\501607\w8\valshheets.dgn
 USER NAME = pier.somb

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. ROUTE 730 (U.S. 51 S.B.)
SECTION 62RS-2
McLEAN COUNTY

SCALE: NOT TO SCALE
DATE: 03/26/07

DRAWN BY: B.B.P.
CHECKED BY: B.C.S.