CONTRACT NO. 70649

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	*	DOUGLAS	8	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D5 PATCHING 2008

SCHEDULE OF QUANTITIES

PAVEMENT PATCHING SCHEDULE

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	DEPTH (inch)	PATCH AREA 44200116 TYPE I 10.0'' (sq. yd)	44200120 TYPE II 10.0'' (sq. yd)	44200124 TYPE III 10.0'' (sq. yd)	44200126 TYPE IV 10.0'' (sq. yd)
35+39	WB	DL	30.0	5.0	10	0	0	16.7	0
37+45	EB	DL	24.0	4.0	10	0	10.7	0	0
37+45	WB	DL	35.0	13.0	10	0	0	0	50.6
38+03	EB	DL	4.0	12.0	10	0	5.3	0	0
38+03		Bi Dir Tu	4.0	12.0	10	0	5.3	0	0
38+03	WB	DL	4.0	12.0	10	0	5.3	0	0
38+65		Bi Dir Tu	4.0	6.0	10	2.7	0	0	0
39+80	EB	DL	25.0	5.0	10	0	13.9	0	0
41+84	WB	DL	14.0	4.0	10	0	6.2	0	0
42+14	EB	DL	25.0	5.0	10	0	13.9	0	0
42+33	WB	DL	8.0	14.0	10	0	12.4	0	0
42+71	EB	DL	8.0	4.0	10	3.6	0	0	0
42+75	EB	DL	8.0	4.0	10	3.6	0	0	0
42+95	EB	DL	12.0	5.0	10	0	6.7	0	0
42+95	WB	DL	20.0	15.0	10	0	0	0	33.3
43+10	EB	DL	14.0	15.0	10	0	0	23.3	0
43+66	EB	DL	80.0	16.0	10	0	0	0	142.2
43+66		Middle	36.0	15.0	10	0	0	0	60
43+66	WB	DL	12.0	15.0	10	0	0	20	0
44+45	WB	DL	12.0	8.0	10	0	10.7	0	0
46+35	EB	DL	19.0	15.0	10	0	0	0	31.7
47+48	EB	DL	19.0	15.0	10	0	0	0	31.7
						9.8	90.4	60.0	349.4
		SHEET TOTALS				(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)
						Use 10 Sq Yd	Use 90 Sq Yd	Use 60 Sq Yd	Use 349 Sq Yd

PLOT DATE = 4/8/2007
FILE NAME = c:\projects\u50907 (v8i)\70469ollsheets.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = pitersonbr

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NOT TO SCALE
DATE: 03/28/07

DRAWN BY: B.B.P.
CHECKED BY: B.J.M.