ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CONTRACT NO. 72798

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(1,2)RS-4	MASON	44	3
STA. 5+10.00		TO STA. 572+82.60		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED. 20% STATE (US 136)		
	Z0048665	PROTECTIVE RAILROAD LIABLITY INSURANCE	L SUM	1	1		
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	68	68		
	40600300	AGGREGATE (PRIME COAT)	TON	356	356		
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	6,512	6,512		
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3,462	3,462		
	40600990	TEMPORARY RAMP	SQ YD	133	133		
	40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	14,954	14,954		
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	513	513		
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7,964	7,964		
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	11,168	11,168		
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2,600	2,600		
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	152,531	152,531		
	44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	1,007	1,007		
	44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SQ YD	117	117		
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,469	4,469		
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
	67100100	MOBILIZATION	L SUM	1	1		
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16,515	16,515		
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	300	300		
	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	150,738	150,738		
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,120	1,120		
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	202	202		
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	279	279		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,835	1,835		
*	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	13,078	13,078		
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	334	334		
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	202	202		
*	78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	137,660	137,660		
	78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	300	300		
	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	786	786		
	78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	279	279		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	934	934		
	78300200	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	EACH	705	705		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. Route 315 (US 136)
Section (1,2)RS-4
MASON COUNTY

SCALE: VERT. HORIZ.
DATE: APRIL 10, 2002
DRAWN BY: JWC
CHECKED BY: RSC

c:\projects\d653003\summary.dgn
3/22/2007
*REF 01

D6 PROJECT: D653003 FILE: SUMMARY.DGN