

CONTRACT NO. 72798

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(1,2)RS-4	MASON	44	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PREFORMED PLASTIC PAVEMENT  
MARKING, TYPE B - LETTERS & SYMBOLS

LOCATION	QUANTITY (SQ FT)
F. A. P. 315 (US 136)	
STA. 14+74.93 RT	
"X" Marking	54
"R" Marking	7.20
RAILROAD OMISSION	
STA. 18+03.15 to 18+15.61	
STA. 20+45.00 LT	
"X" Marking	54
"R" Marking	7.20
STA. 24+63.60	
Lt Turn Arrow	15.60
Rt Turn Arrow	15.60
STA. 25+84.80	
Lt Turn Arrow	15.60
Rt Turn Arrow	15.60
STA. 27+31.80 LT	
Lt Turn Arrow	15.60
Combo Rt Turn & Thru Arrows	26
STA. 27+50.00 LT	
Lt Turn Arrow	15.60
Combo Rt Turn & Thru Arrows	26
Prairie Ridge Road	
STA. 10+66.00	
Lt Turn Arrow	15.60
STA. 11+12.30	
Lt Turn Arrow	15.60
<b>PROJECT TOTAL</b>	<b>300</b>

SCHEDULE OF QUANTITIES

RAISED REFLECTIVE PAVEMENT  
MARKING REMOVAL

LOCATION	QUANTITY (EACH)
F. A. P. 315 (US 136)	
(Beginning of Project to Randolph St.)	2
(Randolph St to Laurel St.)	3
(Laurel St. to McKinley St.)	4
(McKinley St. to Harpham St.)	5
(Harpham St. to Charlotte St.)	10
(Charlotte St. to R.R.)	16
(19+75.50 to TR 1750E)	45
(TR 1750E to TR 1800E)	33
(TR 1800E to TR 1900E)	66
(TR 1900E to TR 1970E)	51
(TR 1970E to TR 2000E)	17
(TR 2000E to TR 2100E)	68
(TR 2100E Ln. to FAS 568)	18
(FAS 568 to TR 2200E)	50
(TR 2200E to TR 2400E)	130
(TR 2400E to TR 2500E)	59
(TR 2500E to TR 2600E)	66
(TR 2600E to TR 2670E)	48
(TR 2670E to End of Project)	14
<b>PROJECT TOTAL</b>	<b>705</b>

RAISED REFLECTIVE  
PAVEMENT MARKER

LOCATION	QUANTITY (EACH)
F. A. P. 315 (US 136)	
(40' Spacing)	
STA. 5+10.00 to 17+73.54	33
STA EQUATION #1	
STA. 17+73.54 (BK) to 0+00.00 (AH)	
STA. 0+00.00 to 18+03.15	46
RAILROAD OMISSION	
STA. 18+03.15 to 18+15.61	
STA. 18+15.61 to 19+75.50	5
STA. 19+75.50 to 24+08.80	48
STA. 24+08.80 to 26+09.80	20
STA. 27+06.80 to 29+07.80	18
STA. 29+07.80 to 35+59.80	69
(80' Spacing)	
STA. 35+59.80 to 173+21.46	173.00
STA EQUATION #2	
STA. 173+21.46 (BK) to 173+25.13 (AH)	
STA. 173+25.13 to 572+82.60	500.00
(40' Spacing)	
Prairie Ridge Rd.	
STA. 10+40.00 to 11+41.00	18
STA. 11+41.00 to 11+55.40	4
<b>PROJECT TOTAL</b>	<b>934</b>

PLOT DATE = 3/22/2007  
 PLOT SCALE = 0.001000  
 USER NAME = jwc

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
F.A.P. Route 315 (US 136)  
Section (1,2)RS-4  
MASON COUNTY  
SCALE: VERT.      DRAWN BY JWC  
          HORIZ.      CHECKED BY RSC  
DATE: MARCH 4, 2007