

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	109 (RS-3)	LOGAN	31	3
STA. 57+64.50		TO STA. 631+30.00		
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				
CONTRACT NO. 72825				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

*100% STATE*

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE 1000 RURAL ROADWAY, FAP 717
20200100	EARTH EXCAVATION	CU YD	48	48
20400805	FURNISHED EXCAVATION, SPECIAL	CU YD	80	80
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ YD	142	142
35800100	PREPARATION OF BASE	SQ YD	483	483
35800200	AGGREGATE BASE REPAIR	TON	27	27
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	32	32
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	81	81
40600300	AGGREGATE (PRIME COAT)	TON	412	412
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6,414	6,414
40600895	CONSTRUCTING TEST TRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,339	1,339
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	147	147
40600990	TEMPORARY RAMP	SQ YD	134	134
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	12,829	12,829
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	217	217
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3,496	3,496
44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	200,985	200,985
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	208	208
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	68	68

REVISIONS	
NAME	DATE
TMJ	02-07

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FAP ROUTE 717 (IL 10)  
SECTION 109 (RS-3)  
LOGAN COUNTY  
SCALE: VERT.      DRAWN BY MLH  
      HORIZ.        CHECKED BY LDB  
DATE AUG 2004