

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	SANGAMON	14	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D-6 PAVEMENT PATCHING 2007				

SUMMARY OF QUANTITIES				URBAN 80% FEDERAL 20% STATE	
CODE NO	ITEM	UNIT	TOTAL	ROADWAY	
				1000	
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQYD	184	184	
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQYD	2,525	2,525	
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQYD	769	769	
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQYD	1,410	1,410	
44213000	PATCHING REINFORCEMENT	SQYD	4,878	4,878	
44213200	SAW CUTS	FOOT	29,342	29,342	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	24	24	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
Z0075300	TIE BARS	EACH	941	941	

PLOT DATE = 3/23/2007  
 FILE NAME = c:\p\projects\72B07\summary.dgn  
 PLOT SCALE = 1/16"  
 USER NAME = masonavj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 FAP 662 (IL 4)  
 D-6 PAVEMENT  
 PATCHING 2007  
 SANGAMON COUNTY  
 SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_