

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	SANGAMON	14	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D-6 PAVEMENT PATCHING 2007				

PATCHING SCHEDULE												
*	STATION	NOTES	LENGTH	WIDTH	AREA	PATCHING CL A, TY1, 8"	PATCHING CL A, TY2, 8"	PATCHING CL A, TY3, 8"	PATCHING CL A, TY4, 8"	SAW CUTS	PATCH REINFORCEMENT	TIE BARS
			FT	FT	SOYD	SOYD	SOYD	SOYD	SOYD	FT	SOYD	EACH
SOUTHBOUND VETERANS PKWY (IL 4) DRIVING LANE												
1	282+50		6	12	8	0	8	0	0	60	8	0
2	282+97	EOP	40	6	27	0	0	0	27	144	27	19
3	283+51		6	12	8	0	8	0	0	60	8	0
4	285+60		6	12	8	0	8	0	0	60	8	0
5	286+25		6	12	8	0	8	0	0	60	8	0
6	288+35		6	12	8	0	8	0	0	60	8	0
7	288+70		6	12	8	0	8	0	0	60	8	0
8	289+56		6	12	8	0	8	0	0	60	8	0
9	289+69		6	12	8	0	8	0	0	60	8	0
10	289+97		7	12	9	0	9	0	0	62	9	0
11	290+65		6	12	8	0	8	0	0	60	8	0
12	291+07		6	12	8	0	8	0	0	60	8	0
13	299+54		6	12	8	0	8	0	0	60	8	0
14	302+94		10	12	13	0	13	0	0	68	13	0
15	303+63		6	12	8	0	8	0	0	60	8	0
16	303+96		16	6	11	0	11	0	0	72	11	0
17	304+47		12	12	16	0	0	16	0	72	16	0
18	304+98		28	12	37	0	0	0	37	104	37	13
19	306+95	EOP	15	6	10	0	10	0	0	69	10	0
20	307+44	EOP	15	6	10	0	10	0	0	69	10	0
21	307+60		6	12	8	0	8	0	0	60	8	0
22	308+00		6	12	8	0	8	0	0	60	8	0
23	309+00		8	12	11	0	11	0	0	64	11	0
24	309+70		6	12	8	0	8	0	0	60	8	0
25	309+97		6	12	8	0	8	0	0	60	8	0
26	313+86		6	12	8	0	8	0	0	60	8	0
27	314+50		6	12	8	0	8	0	0	60	8	0
28	321+05		6	12	8	0	8	0	0	60	8	0
29	321+30		6	12	8	0	8	0	0	60	8	0
30	330+72		15	12	20	0	0	20	0	78	20	0
31	331+94	EOP	15	6	10	0	10	0	0	69	10	0
32	332+21		6	12	8	0	8	0	0	60	8	0
33	332+71		15	6	10	0	10	0	0	69	10	0
34	333+00		15	8	13	0	13	0	0	77	13	0
35	333+46		6	12	8	0	8	0	0	60	8	0
36	333+67		6	12	8	0	8	0	0	60	8	0
37	333+98		6	12	8	0	8	0	0	60	8	0
38	334+55		12	12	16	0	0	16	0	72	16	0
39	334+84		18	12	24	0	0	24	0	84	24	0
40	335+36		20	12	27	0	0	0	27	88	27	0
41	336+08		12	12	16	0	0	16	0	72	16	0
42	336+56		10	12	13	0	13	0	0	68	13	0
43	336+70		6	12	8	0	8	0	0	60	8	0
44	336+87		6	12	8	0	8	0	0	60	8	0
45	349+00		6	12	8	0	8	0	0	60	8	0
46	373+00	EOP	6	12	8	0	8	0	0	60	8	0
47	373+17	RT TURN LN	6	12	8	0	8	0	0	60	8	0
48	374+70	RT TURN LN	12	12	16	0	0	16	0	72	16	0
49	377+85		6	12	8	0	8	0	0	60	8	0
50	384+20		6	12	8	0	8	0	0	60	8	0

PLOT DATE = 3/23/2007  
 FILE NAME = c:\projects\6553487\hatch.dgn  
 USER = mboonard

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE**  
 FAP 662 (IL 4)  
 SECTION D-6 PAVEMENT  
 PATCHING 2007  
 SANGAMON COUNTY  
 SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE