CONTRACT NO. 72B07

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	SANGAMON	14	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PATCHING SCHEDULE

*	STATION	NOTES	LENGTH	WIDTH	AREA	PATCHING CL A, TY1, 8"	PATCHING CL A, TY2, 8"	PATCHING CL A, TY3, 8"	PATCHING CL A, TY4, 8"	SAW CUTS	PATCH REINFORCEMENT	TIE BARS
			FT	FT	SQYD	SQYD	SQYD	SQYD	SQYD	FT	SQYD	EACH
101	450+37	EOP	6	12	8	0	8	0	0	60	8	0
102	450+65		6	12	8	0	8	0	0	60	8	0
103	450+97		6	12	8	0	8	0	0	60	8	0
104	451+45		6	12	8	0	8	0	0	60	8	0
105	452+00		6	12	8	0	8	0	0	60	8	0
106	452+15		6	12	8	0	8	0	0	60	8	0
107	452+38		8	12	11	0	11	0	0	64	11	0
108	452+62		20	6	13	0	13	0	0	84	13	0
109	452+80		20	7	16	0	0	16	0	88	16	0
110	453+16		6	12	8	0	8	0	0	60	8	0
111	453+25		6	12	8	0	8	0	0	60	8	0
112	453+82		6	12	8	0	8	0	0	60	8	0
113	454+55		6	12	8	0	8	0	0	60	8	0
114	455+20		6	12	8	0	8	0	0	60	8	0
115	455+30		8	12	11	0	11	0	0	64	11	0
116	455+45		6	12	8	0	8	0	0	60	8	0
117	455+80		10	12	13	0	13	0	0	68	13	0
118	456+83		6	12	8	0	8	0	0	60	8	0
119	457+00	EOP	10	6	7	0	7	0	0	54	7	0
120	457+10		6	12	8	0	8	0	0	60	8	0
121	457+23		6	12	8	0	8	0	0	60	8	0
122	457+50		6	12	8	0	8	0	0	60	8	0
123	457+70		6	12	8	0	8	0	0	60	8	0
124	458+00		6	12	8	0	8	0	0	60	8	0
125	458+40		6	12	8	0	8	0	0	60	8	0
126	458+52		6	12	8	0	8	0	0	60	8	0
127	458+85		6	12	8	0	8	0	0	60	8	0
128	460+00		6	12	8	0	8	0	0	60	8	0
129	460+23		8	12	11	0	11	0	0	64	11	0
130	460+38		6	12	8	0	8	0	0	60	8	0
131	464+84		6	12	8	0	8	0	0	60	8	0
132	468+46		6	12	8	0	8	0	0	60	8	0
133	469+00		6	12	8	0	8	0	0	60	8	0
134	471+90		6	12	8	0	8	0	0	60	8	0
135	475+15		6	12	8	0	8	0	0	60	8	0
136	477+25		6	12	8	0	8	0	0	60	8	0
137	485+90		25	6	17	0	0	17	0	99	17	12
138	487+16		6	12	8	0	8	0	0	60	8	0
139	487+50		6	12	8	0	8	0	0	60	8	0
140	488+40		6	12	8	0	8	0	0	60	8	0
141	488+70		6	12	8	0	8	0	0	60	8	0
142	489+40		6	12	8	0	8	0	0	60	8	0
143	489+58		6	12	8	0	8	0	0	60	8	0
144	498+97		6	12	8	0	8	0	0	60	8	0
145	500+12		6	12	8	0	8	0	0	60	8	0
146	501+33	EOP	150	6	100	0	0	0	100	474	100	74
147	504+15		6	12	8	0	8	0	0	60	8	0
148	507+97	EOP	6	12	8	0	8	0	0	60	8	0
149	508+20		6	12	8	0	8	0	0	60	8	0
150	508+28		6	12	8	0	8	0	0	60	8	0

PLOT DATE = 3/23/2007
FILE NAME = c:\pr0jects\d653487\ahtsch.dgn
PLOT SCALE = 183.4337 ' / IN.
USER NAME = mcdonl.avj

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

FAP 662 (IL 4)
SECTION D-6 PAVEMENT
PATCHING 2007
SANGAMON COUNTY

SCALE: VERT. HORIZ.

DRAWN BY

DATE

CHECKED BY