CONTRACT NO. 72B07

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	SANGAMON	14	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PATCHING SCHEDULE

*	STATION	NOTES	LENGTH	WIDTH	AREA	PATCHING CL A, TY1, 8"	PATCHING CL A, TY2, 8"	PATCHING CL A, TY3, 8"	PATCHING CL A, TY4, 8"	SAW CUTS	PATCH REINFORCEMENT	TIE BARS
			FT	FT	SQYD	SQYD	SQYD	SQYD	SQYD	FT	SQYD	EACH
151	513+50	EOP	20	8	18	0	0	18	0	92	18	0
152	514+20		6	12	8	0	8	0	0	60	8	0
153	515+20	EOP	30	6	20	0	0	20	0	114	20	14
154	517+06		6	12	8	0	8	0	0	60	8	0
155	521+35	CL	30	6	20	0	0	20	0	114	20	14
156	521+50		6	12	8	0	8	0	0	60	8	0
157	521+75		16	12	21	0	0	21	0	80	21	0
158	523+00		10	12	13	0	13	0	0	68	13	0
159	523+12		6	12	8	0	8	0	0	60	8	0
160	523+65		6	12	8	0	8	0	0	60	8	0
161	523+80		7	12	9	0	9	0	0	62	9	0
162	524+10		6	12	8	0	8	0	0	60	8	0
163	525+10		12	12	16	0	0	16	0	72	16	0
164	529+15		6	12	8	0	8	0	0	60	8	0
165	540+56		6	12	8	0	8	0	0	60	8	0
166	548+25		50	12	67	0	0	0	67	148	67	24
167	549+00		12	12	16	0	0	16	0	72	16	0
168	549+25		6	12	8	0	8	0	0	60	8	0
169	549+50	EOP	30	6	20	0	0	20	0	114	20	14
170	561+00		6	12	8	0	8	0	0	60	8	0
171	561+35		6	12	8	0	8	0	0	60	8	0
172	565+60	EOP	30	6	20	0	0	20	0	114	20	14
173	656+85		6	12	8	0	8	0	0	60	8	0
174	566+00		8	12	11	0	11	0	0	64	11	0
175	566+15	EOP	25	6	17	0	0	17	0	99	17	12
176	571+70		6	12	8	0	8	0	0	60	8	0
177	575+75		6	12	8	0	8	0	0	60	8	0
178	578+00		40	6	27	0	0	0	27	144	27	19
179	583+10	CL	60	6	40	0	0	0	40	204	40	29
180	588+50		20	12	27	0	0	0	27	88	27	0
181	598+50		6	12	8	0	8	0	0	60	8	0
182	619+30	EOP	50	6	33	0	0	0	33	174	33	24
183	626+85		10	12	13	0	13	0	0	68	13	0
184	627+25		6	12	8	0	8	0	0	60	8	0
185	627+50		6	12	8	0	8	0	0	60	8	0
186	628+50		40	6	27	0	0	0	27	144	27	19
187	633+50		6	12	8	0	8	0	0	60	8	0
188	635+00		20	12	27	0	0	0	27	88	27	0
189	638+70	EOP	6	12	8	0	8	0	0	60	8	0
	SOUTHBOUND VETERANS PKWY (IL 4) PASSING LANE											
190	319+80		15	6	10	0	10	0	0	69	10	0
191	320+70	EOP	35	6	23	0	0	23	0	129	23	17
192	321+35		6	12	8	0	8	0	0	60	8	0
193	321+64		6	12	8	0	8	0	0	60	8	0
194	322+00		6	12	8	0	8	0	0	60	8	0
195	322+96		6	12	8	0	8	0	0	60	8	0
196	323+37		6	12	8	0	8	0	0	60	8	0
197	323+67		6	12	8	0	8	0	0	60	8	0
198	325+10		6	12	8	0	8	0	0	60	8	0
199	338+81		6	12	8	0	8	0	0	60	8	0
200	340+77		6	12	8	0	8	0	0	60	8	0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

FAP 662 (IL 4)
SECTION D-6 PAVEMENT
PATCHING 2007
SANGAMON COUNTY

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/23/2007
FILE NAME = o:\projects\d653487\sht\sch.dgn
PLOT SCALE = 128.4337 ' / IN.
USER NAME = madonsvj