CONTRACT NO. 72B07

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 662 | * | SANGAMON | 14 | 9 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

PATCHING SCHEDULE

| * | STATION | NOTES | LENGTH | WIDTH | AREA | PATCHING CL A, TY1, 8" | PATCHING CL A, TY2, 8" | PATCHING CL A, TY3, 8" | PATCHING CL A, TY4, 8" | SAW CUTS | PATCH REINFORCEMENT | TIE BARS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | FT | FT | SQYD | SQYD | SQYD | SQYD | SQYD | FT | SQYD | EACH |
| 251 | 523+70 | | 7 | 12 | 9 | 0 | 9 | 0 | 0 | 62 | 9 | 0 |
| 252 | 523+80 | | 7 | 12 | 9 | 0 | 9 | 0 | 0 | 62 | 9 | 0 |
| 253 | 525+10 | | 12 | 12 | 16 | 0 | 0 | 16 | 0 | 72 | 16 | 0 |
| 254 | 549+00 | | 12 | 12 | 16 | 0 | 0 | 16 | 0 | 72 | 16 | 0 |
| 255 | 566+00 | | 8 | 12 | 11 | 0 | 11 | 0 | 0 | 64 | 11 | 0 |
| 256 | 566+15 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 257 | 566+40 | | 8 | 12 | 11 | 0 | 11 | 0 | 0 | 64 | 11 | 0 |
| 258 | 571+90 | EOP | 100 | 6 | 67 | 0 | 0 | 0 | 67 | 324 | 67 | 49 |
| 259 | 580+00 | CL | 40 | 6 | 27 | 0 | 0 | 0 | 27 | 144 | 27 | 19 |
| 260 | 583+10 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 261 | 634+00 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 262 | 641+20 | | 20 | 12 | 27 | 0 | 0 | 0 | 27 | 88 | 27 | 0 |
| 263 | 644+60 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| | *NORTHBOUND VETERANS PKWY (IL 4) DRIVING LANE* | | | | | | | | | | | |
| 264 | 640+99 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 265 | 640+64 | | 6 | 6 | 4 | 4 | 0 | 0 | 0 | 42 | 4 | 0 |
| 266 | 640+40 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 267 | 638+62 | | 6 | 6 | 4 | 4 | 0 | 0 | 0 | 42 | 4 | 0 |
| 268 | 637+55 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 269 | 637+27 | | 27 | 12 | 36 | 0 | 0 | 0 | 36 | 102 | 36 | 13 |
| 270 | 635+29 | | 15 | 6 | 10 | 0 | 10 | 0 | 0 | 69 | 10 | 0 |
| 271 | 632+98 | | 20 | 6 | 13 | 0 | 13 | 0 | 0 | 84 | 13 | 0 |
| 272 | 629+37 | | 6 | 6 | 4 | 4 | 0 | 0 | 0 | 42 | 4 | 0 |
| 273 | 629+17 | | 6 | 6 | 4 | 4 | 0 | 0 | 0 | 42 | 4 | 0 |
| 274 | 625+45 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 275 | 625+26 | | 8 | 12 | 11 | 0 | 11 | 0 | 0 | 64 | 11 | 0 |
| 276 | 622+06 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 277 | 621+75 | | 16 | 6 | 11 | 0 | 11 | 0 | 0 | 72 | 11 | 0 |
| 278 | 621+37 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 279 | 614+80 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 280 | 612+30 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 281 | 610+30 | | 6 | 6 | 4 | 4 | 0 | 0 | 0 | 42 | 4 | 0 |
| 282 | 607+20 | | 60 | 6 | 40 | 0 | 0 | 0 | 40 | 204 | 40 | 29 |
| 283 | 572+70 | | 12 | 12 | 16 | 0 | 0 | 16 | 0 | 72 | 16 | 0 |
| 284 | 572+40 | | 20 | 6 | 13 | 0 | 13 | 0 | 0 | 84 | 13 | 0 |
| 285 | 562+50 | | 60 | 6 | 40 | 0 | 0 | 0 | 40 | 204 | 40 | 29 |
| 286 | 561+45 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 287 | 555+34 | | 30 | 6 | 20 | 0 | 0 | 20 | 0 | 114 | 20 | 14 |
| 288 | 554+65 | | 75 | 6 | 50 | 0 | 0 | 0 | 50 | 249 | 50 | 37 |
| 289 | 545+90 | | 20 | 6 | 13 | 0 | 13 | 0 | 0 | 84 | 13 | 0 |
| 290 | 544+85 | | 30 | 12 | 40 | 0 | 0 | 0 | 40 | 108 | 40 | 14 |
| 291 | 544+10 | | 20 | 6 | 13 | 0 | 13 | 0 | 0 | 84 | 13 | 0 |
| 292 | 542+10 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 293 | 542+00 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 294 | 541+40 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 295 | 539+85 | | 6 | 12 | 8 | 0 | 8 | 0 | 0 | 60 | 8 | 0 |
| 296 | 537+82 | | 20 | 6 | 13 | 0 | 13 | 0 | 0 | 84 | 13 | 0 |
| 297 | 537+16 | | 25 | 6 | 17 | 0 | 0 | 17 | 0 | 99 | 17 | 12 |
| 298 | 536+17 | | 78 | 12 | 104 | 0 | 0 | 0 | 104 | 204 | 104 | 38 |
| 299 | 536+15 | | 30 | 6 | 20 | 0 | 0 | 20 | 0 | 114 | 20 | 14 |
| 300 | 535+36 | | 15 | 6 | 10 | 0 | 10 | 0 | 0 | 69 | 10 | 0 |

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

FAP 662 (IL 4)
SECTION D-6 PAVEMENT
PATCHING 2007
SANGAMON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 3/23/2007
FILE NAME = c:\projects\d853487\shtsch.dgn
PLOT SCALE = 108.4337 ' / IN.
USER NAME = mcdonsvj