

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		SANGAMON	14	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PATCHING SCHEDULE												
*	STATION	NOTES	LENGTH	WIDTH	AREA	PATCHING CL A, TY1, 8"	PATCHING CL A, TY2, 8"	PATCHING CL A, TY3, 8"	PATCHING CL A, TY4, 8"	SAW CUTS	PATCH REINFORCEMENT	TIE BARS
			FT	FT	SOYD	SOYD	SOYD	SOYD	SOYD	SOYD	FT	SOYD
351	245+75		6	6	4	4	0	0	0	42	4	0
352	245+62		6	6	4	4	0	0	0	42	4	0
353	102+00	LOOP	8	12	11	0	11	0	0	64	11	0
NORTHBOUND VETERANS PKWY (IL 4) PASSING LANE												
354	643+90		6	12	8	0	8	0	0	60	8	0
355	641+41		12	12	16	0	0	16	0	72	16	0
356	641+23		12	12	16	0	0	16	0	72	16	0
357	641+00		12	12	16	0	0	16	0	72	16	0
358	640+75		6	12	8	0	8	0	0	60	8	0
359	639+00		60	6	40	0	0	0	40	204	40	29
360	638+20		60	12	80	0	0	0	80	168	80	29
361	637+92		100	6	67	0	0	0	67	324	67	49
362	637+50		6	12	8	0	8	0	0	60	8	0
363	635+35		60	6	40	0	0	0	40	204	40	29
364	631+78		6	6	4	4	0	0	0	42	4	0
365	630+75		60	6	40	0	0	0	40	204	40	29
366	629+47		6	6	4	4	0	0	0	42	4	0
367	628+34		6	6	4	4	0	0	0	42	4	0
368	627+94		9	12	12	0	12	0	0	66	12	0
369	625+45		6	6	4	4	0	0	0	42	4	0
370	624+40		6	6	4	4	0	0	0	42	4	0
371	620+09		18	6	12	0	12	0	0	78	12	0
372	618+45		20	12	27	0	0	0	27	88	27	0
373	618+12	LT TURN LN	6	12	8	0	8	0	0	60	8	0
374	618+12		6	6	4	4	0	0	0	42	4	0
375	617+81		6	12	8	0	8	0	0	60	8	0
376	617+20		25	6	17	0	0	17	0	99	17	12
377	615+30		14	12	19	0	0	19	0	76	19	0
378	614+20		6	12	8	0	8	0	0	60	8	0
379	613+90		60	6	40	0	0	0	40	204	40	29
380	610+85		6	12	8	0	8	0	0	60	8	0
381	609+20		15	6	10	0	10	0	0	69	10	0
382	584+25		15	12	20	0	0	20	0	78	20	0
383	580+80	LT TURN LN	6	12	8	0	8	0	0	60	8	0
384	579+80	LT TURN LN	6	12	8	0	8	0	0	60	8	0
385	578+80	LT TURN LN	6	12	8	0	8	0	0	60	8	0
386	578+50	LT TURN LN	12	12	16	0	0	16	0	72	16	0
387	576+60		6	6	4	4	0	0	0	42	4	0
388	572+70		12	12	16	0	0	16	0	72	16	0
389	572+50		6	12	8	0	8	0	0	60	8	0
390	537+12		6	12	8	0	8	0	0	60	8	0
391	530+60		6	6	4	4	0	0	0	42	4	0
392	530+17		6	6	4	4	0	0	0	42	4	0
393	529+93		6	12	8	0	8	0	0	60	8	0
394	529+30		6	6	4	4	0	0	0	42	4	0
395	505+00		6	6	4	4	0	0	0	42	4	0
396	488+80	LT TURN LN	6	6	4	4	0	0	0	42	4	0
397	488+65	LT TURN LN	14	14	22	0	0	22	0	84	22	0
398	488+50	LT TURN LN	6	14	9	0	9	0	0	68	9	0
399	488+20	LT TURN LN	15	14	23	0	0	23	0	86	23	0
400	488+00	LT TURN LN	14	14	22	0	0	22	0	84	22	0

PLOT DATE = 3/23/2007
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = medonovj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

FAP 662 (IL 4)
 SECTION D-6 PAVEMENT
 PATCHING 2007
 SANGAMON COUNTY

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE