

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE
			1000
			TOTAL QTY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.2
40600300	AGGREGATE (PRIME COAT)	TON	16.9
40600990	TEMPORARY RAMP	SQ YD	80
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	711
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8.462
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	650
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	10,590
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	109
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	10,590
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	41
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	41

*SPECIALTY ITEMS

QUANTITIES
FAP 304 (IL 96)
SECTION 4RS-4
PIKE COUNTY