

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	68	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FAP 332 (IL 1); FAP 328 (US 45)				
** 101B-1; (BSR-1)B-1				
*** WABASH / WAYNE				

CODED PAYITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	SN 096-0020 (US 45)		SN 093-0005 (IL 1)	
				WAYNE COUNTY 80% FEDERAL / 20% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE		WABASH COUNTY 80% FEDERAL / 20% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE	
				I000-2A	X080-2A	I000-2A	X080-2A
20200100	EARTH EXCAVATION	CU YD	233	134		99	
20400800	FURNISHED EXCAVATION	CU YD	96			96	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5	0.5			
28000300	TEMPORARY DITCH CHECKS	EACH	6	3		3	
28000400	PERIMETER EROSION BARRIER	FOOT	2126	746		1380	
28000500	INLET AND PIPE PROTECTION	EACH	2	2			
35650500	BASE COURSE WIDENING 10"	SQ YD	504	354		150	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	31	31			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	223	58		165	
40600300	AGGREGATE (PRIME COAT)	TON	2	1		1	
40600990	TEMPORARY RAMP	SQ YD	28	28			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	13	5		8	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	47	10	9	28	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	295	116		179	
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	24				24
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	146		146		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	89				89
44000700	APPROACH SLAB REMOVAL	SQ YD	1016	1016			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	554	297		257	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2		1		1
50102400	CONCRETE REMOVAL	CU YD	9			9	
50105220	PIPE CULVERT REMOVAL	FOOT	60	60			
50300260	BRIDGE DECK GROOVING	SQ YD	753		144		609
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.6		1.6		
50300300	PROTECTIVE COAT	SQ YD	763		154		609
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	299				299
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1383		1383		
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	4156				4156
50800205	REINFORCEMENT BARS (EPOXY COATED)	POUND	11040		3250		7790
50800515	BAR SPLICERS	EACH	216		42		174
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	82		82		

Plot Date: 3/19/2007
 Plot Time: 9:48:44 AM
 Plotted By: mb-illard
 Pen Table: f001.tbl
 File Name: I:\000005\Constr\Construction\Drawn\03_Summary.ydgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET 1 OF 3

SCALE: VERT. N/A
 HORIZ. N/A
 DATE 03/15/07

DRAWN BY KMO
 CHECKED BY SSM