

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	68	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FAP 332 (IL 1); FAP 328 (US 45)				
** 101B-1; (8BR-1)B-1				
*** WABASH / WAYNE				

CODED PAYITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	SN 096-0020 (US 45)		SN 093-0005 (IL 1)	
				WAYNE COUNTY 80% FEDERAL / 20% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE		WABASH COUNTY 80% FEDERAL / 20% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE	
				I000-2A	X080-2A	I000-2A	X080-2A
50901050	STEEL RAILING, TYPE SM	FOOT	458		126		332
51500100	NAME PLATES	EACH	2		1		1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	70	70			
54213450	END SECTIONS 15"	EACH	4	4			
59000200	EPOXY CRACK INJECTION	FOOT	45				45
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	900	500		400	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8	4		4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	8	4		4	
63200310	GUARDRAIL REMOVAL	FOOT	875	404		471	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	3		3	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1		1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5		0.5	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5		0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5		0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	5		5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2369	1591		778	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	925	350		575	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1000	450		550	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4829	2895		1934	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	242			242	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	22	10		12	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	26	8		18	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	4		4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1900	1206		694	
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	281	281			
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	252		252		
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	598		299		299

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 2 OF 3

SCALE: VERT. N/A
HORIZ. N/A
DATE: 03/15/07

DRAWN BY: KMO
CHECKED BY: SSM