CONTRACT NO. 74003

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	68	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP 332 (IL 1; FAP 328 (US 45)
** 101B-1; (BBR-1)B-1
*** WABASH / WAYNE

GUARDRAIL

LOCATION	SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
STATION TO STATION		FOOT	FOOT	EACH	EACH	EACH	EACH
SN 096-0020 (US 45) ENDSLEY CREEK							
STA 717+89.10 TO STA 719+20.70	LT		100	1	1	2	1
STA 718+20.70 TO STA 719+22.11	LT	101					
STA 718+01.60 TO STA 719+20.60	RT		87.5	1	1	2	1
STA 718+20.60 TO STA 719+21.87	RT	101					
STA 720+04.32 TO STA 721+04.32	LT	101					
STA 720+05.71 TO STA 722+49.58	LT		212.5	1	1	2	1
STA 720+03.93 TO STA 721+03.93	RT	101					
STA 720+04.98 TO STA 721+37.08	RT		100	1	1	2	1
SUBTOTAL		404	500	4	4	8	4
SN 093-0005 (IL 1) BONPAS CREEK							
STA 146+22.46 TO STA 148+47.00	LT	114	100	1	1	4	1
STA 146+34.96 TO STA 148+47.00	RT	112	100	1	1	4	1
STA 150+13.00 TO STA 152+94.25	LT	119	100	1	1	5	1
STA 150+13.00 TO STA 152+06.75	RT	126	100	1	1	5	1
SUBTOTAL		471	400	4	4	18	4
PROJECT TOTAL		875	900	8	8	26	8

EROSION CONTROL

LOCATION	SIDE	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
STATION TO STATION		EACH	FOOT	EACH
SN 096-0020 (US 45) ENDSLEY CREEK				
STA 717+11.69 TO STA 719+21.59	LT		240	
STA 716+79.86	LT			1
STA 717+18.81	RT			1
STA 717+65.00	RT	1		
STA 717+75.00 TO STA 719+21.59	RT		148	
STA 720+04.59 TO STA 722+50.00	LT		246	
STA 720+04.59 TO STA 721+15.00	RT		112	
STA 721+25.00	RT	1		
STA 722+75.00	LT	1		
SUBTOTAL		3	746	2
SN 093-0005 (IL 1) BONPAS CREEK				
STA 146+00.00 TO STA 153+13.54	LT		688	
STA 145+15.97 TO STA 152+30.00	RT		692	
STA 148+25.00	LT	1		
STA 148+25.00	RT	1		
STA 150+25.00	LT	1		
SUBTOTAL		3	1380	
PROJECT TOTAL		6	2126	2

REMOVAL ITEMS

LOCATION	SIDE	PIPE CULVERT REMOVAL	CONCRETE REMOVAL
STATION TO STATION		FOOT	CU YD
SN 096-0020 (US 45) ENDSLEY CREEK			
STA 717+18.81 TO STA 717+48.77	RT	30	
STA 717+28.61 TO STA 717+56.53	LT	30	
SUBTOTAL		60	
SN 093-0005 (IL 1) BONPAS CREEK			
STA 148+46.92 TO STA 148+66.84			4.5
STA 149+93.16 TO STA 150+13.08			4.5
SUBTOTAL			9
PROJECT TOTAL		60	9

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET 2 OF 3

SCALE: VERT. NONE HORIZ. NONE
DATE 03/15/07

DRAWN BY KMO
CHECKED BY SSM

Plot Date: 3/19/2007
Plot Time: 9:40:34 AM
Plotted By: nbullard
Pen Table: Cont.tbl
Filename: S:\IDOT\Construction\Plans\04_Schedules.dgn