

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	68	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* FAP 332 (IL 1); FAP 328 (US 45)				
** 101B-1; (8BR-1B-1)				
*** WABASH / WAYNE				

EARTHWORK					
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	SHRINKAGE FACTOR	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION TO STATION	CU YD	CU YD		CU YD	CU YD
SN 096-0020 (US 45) ENDSLEY CREEK					
STA 716+69.16 TO STA 723+08.63	134	103	25	64	39
SUBTOTAL	134	103		64	39
SN 093-0005 (IL 1) BONPAS CREEK					
STA 145+20.00 TO STA 153+00.00	99	74	25	209	-135
SUBTOTAL	99	74		209	-135
PROJECT TOTAL	233	177		273	-96

PAVEMENT MARKING							
LOCATION	SIDE	PAINT PAVEMENT MARKING			RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL
		LINE 4" SOLID WHITE	LINE 4" SOLID YELLOW	LINE 6" SKIP DASH YELLOW			
STATION TO STATION		FOOT	FOOT	FOOT	EACH	SQ FT	SQ FT
SN 096-0020 (US 45) ENDSLEY CREEK							
STA 716+01.34 TO STA 717+88.09	RT						187
STA 716+01.34 TO STA 718+88.09	LT						230
STA 716+01.34 TO STA 723+24.84	LT/RT	1448			10	482	71
STA 716+01.34 TO STA 723+24.84	CL		1447			724	24
STA 717+19.95 TO STA 722+01.10	LT/RT						321
STA 717+24.53 TO STA 722+06.52	LT/RT						321
STA 720+38.09 TO STA 723+74.84	LT						250
STA 721+38.09 TO STA 723+24.84	RT						187
SUBTOTAL		1448	1447		10	1206	1591
SN 093-0005 (IL 1) BONPAS CREEK							
STA 144+19.71 TO STA 154+17.53	LT/RT				12		52
STA 144+32.21 TO STA 154+93.00	LT/RT						52
STA 144+19.71 TO STA 147+24.38 (BK)	LT/RT	609				203	111
STA 144+19.71 TO STA 147+24.38 (BK)	CL			76		16	10
STA 144+32.21 TO STA 147+24.38 (BK)	LT/RT						97
STA 147+55.17 (AH) TO STA 154+17.53	CL			166		33	
STA 147+55.17 (AH) TO STA 147+83.00	CL						1
STA 147+55.17 (AH) TO STA 147+83.00	LT/RT						1
STA 147+55.17 (AH) TO STA 154+17.53	LT/RT	1325				442	
STA 147+24.38 (BK) TO STA 144+14.71	CL						
STA 147+55.17 (AH) TO STA 154+17.53	LT/RT						221
STA 147+55.71 (AH) TO STA 153+93.00	LT/RT						213
STA 150+63.08 TO STA 154+17.53	CL						12
STA 150+63.08 TO STA 154+17.53	LT/RT						8
SUBTOTAL		1934		242	12	694	778
PROJECT TOTAL		4829		242	22	1900	2369

DRAINAGE			
LOCATION	SIDE	PIPE CULVERTS, CLASS D, TYPE 1 15"	END SECTIONS 15"
STATION TO STATION		FOOT	EACH
SN 096-0020 (US 45) ENDSLEY CREEK			
STA 716+79.86 TO STA 717+17.55	LT	38	2
STA 717+18.81 TO STA 717+50.00	RT	32	2
SUBTOTAL		70	4
SN 093-0005 (IL 1) BONPAS CREEK			
SUBTOTAL			
PROJECT TOTAL		70	4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SHEET 3 OF 3

SCALE: VERT. NONE
 HORIZ. NONE
 DATE 03/15/07

DRAWN BY KMO
 CHECKED BY SSM