

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(F-1,1)RS-4	CLARK	46	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

LOCATION OF WORK:

IL ROUTE 1
CLARK COUNTY
STATION 37+30.00
TO
STATION 63+76.26
RURAL 2-LANE
80% FEDERAL
20% STATE
1000-2A

IL ROUTE 1
CLARK COUNTY
STATION 63+76.26
TO
STATION 141+85.00
RURAL 3-LANE
80% FEDERAL
20% STATE
1000-2A

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	7.0	0.0	7.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,325.0	1,067.0	4,258.0
40600300	AGGREGATE (PRIME COAT)	TON	41.0	6.0	35.0
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	1,908.0	0.0	1,908.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0	0.0
40600990	TEMPORARY RAMP	SQ YD	1,162.0	123.0	1,039.0
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	55.0	0.0	55.0
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	353.0	353.0	0.0
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,405.0	543.0	2,862.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	468.0	0.0	468.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	10,668.0	10,668.0	0.0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	36,933.0	0.0	36,933.0
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	195.0	0.0	195.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	29.0	0.0	29.0
44200176	PAVEMENT PATCHING, TYPE I, 15 INCH	SQ YD	58.0	49.0	9.0
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	197.0	52.0	145.0
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	55.0	0.0	55.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	3.0	0.0	3.0
60255500	MANHOLES TO BE ADJUSTED	EACH	6.0	0.0	6.0
60604000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (DOWELLED)	FOOT	29.0	0.0	29.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4.0	2.0	2.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0	0.0
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.0	0.0	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,396.0	953.0	5,443.0
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	599.0	0.0	599.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	22,068.0	5,422.0	16,646.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	687.0	0.0	687.0

PLOT DATE = 3/13/2007
FILE NAME = c:\pcc\jobs\74143\74143test.dgn
PLOT SCALE = 28.0000 / IN.
USER NAME = staff@nwk