

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	2,3,4RS-2	EFF./CLAY	17	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000	1000
				EFFINGHAM COUNTY	CLAY COUNTY
20201006	GRADING AND SHAPING SHOULDERS	UNIT	851	609	242
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16976	12168	4808
40600300	AGGREGATE (PRIME COAT)	TON	339	243	96
40600990	TEMPORARY RAMP	SQ YD	175	146	29
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	14260	10221	4039
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	169763	121679	48084
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	1579	1243	336
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	167	150	17
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	104	76	28
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1116	720	396
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	2.1	0.9
67100100	MOBILIZATION	L SUM	1	0.7	0.3
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.7	0.3
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.7	0.3
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	17675	12567	5108
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1964	1396	568
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	162410	122510	39900
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	779	565	214

* SPECIALTY ITEMS

PLOT DATE = 5/29/2007
 FILE NAME = C:\pwworkspace\74160\74160.dwg
 PLOT SCALE = 100.0000 / 1 IN.
 USER NAME = user1234

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____