CONTRACT NO. 74160

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	(2,3,4)RS-2	EFF./CLAY	17	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT MIX ASPHALT SURFACE COURSE MIX "C", N TO	HOT- MIX ASPHALT SURFACE REMOVAL 1 1/2"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER
	FT	FT	SQ YD	GALLON	TON	TON	SQ YD	FOOT	SQ FT	FOOT	EACH
EFFINGHAM COUNTY											
STA 349+65 TO STA 421+55.2	7190.2	26	20771.7	2077.2	41.5	1744.8	20771.7	719	239.7	16178	90.9
STA 421+52 TO STA 435+06.0	1354.01	26	3911.6	391.2	7.8	328.6	3911.6	135.4	45.1	3046.5	18
STA 435+22.9 TO STA 437+50.0	227.15	26	656.2	65.6	1.3	55.1	656.2	22.7	7.6	511.1	3.9
STA 437+50 TO STA 439+07.6	157.64	28	490.4	49.0	1.0	41.2	490.4	15.8	5.3	354.7	3
BRIDGE OMISSION											
STA 440+27.4 TO STA 442+50.0	222.64	28	692.7	69.3	1.4	58.2	692.7	22.3	7.4	500.9	3.8
STA 442+50 TO STA 444+85.2	235.21	26	679.5	68.0	1.4	57.1	679.5	23.5	7.8	529.2	4
STA 445+26.5 TO STA 487+50.0	4223.55	26	12201.4	1220.1	24.4	1024.9	12201.4	422.4	140.8	9503	53.8
STA 487+50 TO STA 504+00.0	1650	30	5500	550.0	11.0	462	5500	165	55.0	3712.5	21.7
BRIDGE OMISSION											
STA 506+65.8 TO STA 521+00.0	1434.19	30	4780.6	478.1	9.6	401.6	4780.6	143.4	47.8	3226.9	19
STA 521+50.7 TO STA 535+28.7	1377.96	26	3980.8	398.1	8.0	334.4	3980.8	137.8	45.9	3100.4	18.3
STA 544+14.6 TO STA 620+00.0	7585.4	26	21913.4	2191.3	43.8	1840.7	21913.4	758.5	252.8	17067.2	95.9
STA 620+00 TO STA 634+52.0	1452	30	4840	484.0	9.7	406.6	4840	145.2	48.4	3267	19.2
BRIDGE OMISSION											
STA 636+38.8 TO STA 639+01.4	262.66	30	875.5	87.6	1.8	73.5	875.5	26.3	8.8	591	4.3
BRIDGE OMISSION											
STA 640+76.7 TO STA 650+73.3	996.57	30	3321.9	332.2	6.6	279	3321.9	99.7	33.2	2242.3	13.5
STA 656+42.8 TO STA 746+36.0	8993.14	24	23981.7	2398.2	48.0	2014.5	23981.7	899.3	299.8	20234.6	113.5
STA 751+49.1 TO STA 796+77.2	4528.13	26	13081.3	1308.1	26.2	1098.8	13081.3	452.8	150.9	10188.3	57.7
CLAY COUNTY											
STA 796+77 TO STA 806+43.0	966	26	2790.7	279.1	5.6	234.4	2790.7	96.6	32.2	2173.5	13.1
BRIDGE OMISSION											
STA 806+90.6 TO STA 967+50.0	16059.36	26	46393.7	4639.4	92.8	3897.1	46393.7	1605.9	535.3	36133.6	201.8
TOTALS	58915.81		170863.	17086.3	342	14353	170863	5892	1964	132561	755

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/29/2007
FILE NAME = c:\projects\74160\sht\sch_74160.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = wadarpw