

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	•	**	15	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

- D-7 JOINT REPAIRS 2007-1
- ** FAYETTE

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	SCHEDULE OF QUANTITIES
5	EXISTING TYPICAL CROSS SECTION
6	STAGE I & II CONSTRUCTION TYPICAL
7-8	STAGE I TRAFFIC CONTROL
9-10	STAGE II TRAFFIC CONTROL
11	PLAN VIEW
12-13	EXPANSION JOINT & REBAR DETAILS
14-16	BEARING DETAILS
17	PREFORMED JOINT STRIP SEAL
18	BAR SPLICER ASSEMBLY

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE PROJECT IS LOCATED, APPROXIMATELY 1.0 MILES WEST OF THE (I-70) / (US 51) INTERCHANGE, JUST NORTH OF VANDALIA IN FAYETTE COUNTY. STRUCTURE # 026-0013 CROSSES (IL-185) IN AN EASTERLY DIRECTION.

THE WORK INCLUDED IN THIS PROJECT WILL CONSIST OF, REMOVING THE EXISTING PREFORMED JOINT SEAL EXPANSION JOINTS AND REPLACING THEM WITH PREFORMED JOINT STRIP SEAL EXPANSION JOINTS, REMOVING EXISTING ABUTMENT BEARINGS AND REPLACING THEM WITH ELASTOMERIC BEARING ASSEMBLIES, REMOVING PART OF THE EXISTING BITUMINOUS SHOULDER AND REPLACING IT WITH CONCRETE BASE COURSE WIDENING 10" AND ALL OTHER WORK NECESSARY TO COMPLETE THIS PROJECT.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK; HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.

TEMPORARY CONCRETE BARRIERS, STATE OWNED, ARE LOCATED AT THE MAINTENANCE YARD IN FLORA. A MINIMUM OF 48 HOURS NOTICE WILL BE REQUIRED TO ARRANGE PICK UP AND RETURN OF THE BARRIERS. STATE MAINTENANCE FORCES WILL NOT LOAD OR UNLOAD THE BARRIERS. CONNECTING PINS, DOWEL BARS, STYROFOAM PADS AND DRIFT PINS USED WITH THE BARRIERS SHALL BE FURNISHED BY THE CONTRACTOR. THE COST OF NECESSARY CONNECTING PINS, DOWEL BARS AND STYROFOAM PADS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER FOOT (METER) FOR TEMPORARY CONCRETE BARRIER, STATE OWNED.

ALL ELEVATIONS SHOWN IN PLANS ARE BASED ON U.S.G.S. DATUM.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATION AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 800-892-0123. A MINIMUM OF 96 HOURS ADVANCE NOTICE IS REQUESTED.

LIST OF HIGHWAY STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-01	AREAS OF REINFORCEMENT REBARS
001006	DECIMAL OF AN INCH AND OF A FOOT
421001-01	BAR REINFORCEMENT FOR CRC PAVEMENT
701400-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
701402-05	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
701406-04	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
701426-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
702001-06	TRAFFIC CONTROL DEVICES
780001-01	TYPICAL PAVEMENT MARKINGS
781001-02	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**INDEX OF SHEETS,
 HIGHWAY STANDARDS
 & GENERAL NOTES**
SN 026-0013

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____

Rev.