

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TO	.	**	12	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- D-7 JOINT REPAIRS 2007-1
- FAYETTE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		100% STATE SFTY-2A
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	391	391
44004250	PAVED SHOULDER REMOVAL	SQ YD	391	391
50102400	CONCRETE REMOVAL	CU YD	12.3	12.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.6	12.6
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1530	1530
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	14	14
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1700	1700
50800515	BAR SPLICERS	EACH	24	24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	86	86
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	7	7
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	7	7
52100520	ANCHOR BOLTS, 1"	EACH	28	28
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	1
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	5810	5810
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1937	1937
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	400	400
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	320	320
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2887	2887
*78100300	REPLACEMENT REFLECTOR	EACH	22	22
78300100	PAVEMENT MARKING REMOVAL	SQ FT	963	963
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	22	22
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE: HORIZ.

DRAWN BY: CHECKED BY:

PLT DATE: DATE: PLS SCALE: SCALE: USER NAME: USER:

Rev.