

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	**	15	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

- * D-7 JOINT REPAIRS 2007-1
- ** FAYETTE

LOCATION		DISCRIPTION PAVEMENT MARKING STRIPE	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	PAVEMENT MARKING REMOVAL SQ FT
STATION / OFFSET	TO STATION / OFFSET			
STAGE I				
440+29.44 / RT 56.00'	450+29.44 / RT 40.50'	SOLID WHITE	329.9	
450+29.44 / RT 40.50'	455+29.44 / RT 40.50'	SOLID WHITE	165.2	
455+29.44 / RT 40.50'	457+31.33 / RT 40.50'	SOLID WHITE	66.7	
448+01.00 / RT 32.00'	450+29.44 / RT 28.50'	SOLID YELLOW	75.7	
450+29.44 / RT 28.50'	455+29.44 / RT 28.50'	SOLID YELLOW	165.6	
455+29.44 / RT 28.50'	457+31.33 / RT 28.50'	SOLID YELLOW	66.7	
457+31.33 / RT 28.50'	460+32.00 / RT 32.00'	SOLID YELLOW	99.6	
440+29.44	457+31.33	4" SKIP DASH		141.8
448+01.00	460+32.00	4" SOLID		410.3
STAGE II				
440+29.26 / RT 32.00'	450+29.26 / RT 47.50'	SOLID YELLOW	330.5	
450+29.26 / RT 47.50'	455+29.26 / RT 47.50'	SOLID YELLOW	164.9	
455+29.26 / RT 47.50'	457+31.33 / RT 47.50'	SOLID YELLOW	66.7	
448+01.00 / RT 56.00'	450+29.26 / RT 59.50'	SOLID WHITE	75.1	
450+29.26 / RT 59.50'	455+29.26 / RT 59.50'	SOLID WHITE	164.5	
455+29.26 / RT 59.50'	457+31.33 / RT 59.50'	SOLID WHITE	66.5	
457+31.33 / RT 59.50'	460+32.00 / RT 56.00'	SOLID WHITE	99.0	
448+01.00	460+32.00	4" SOLID		410.3
TOTAL =			1936.6	962.4

LOCATION		PAVED SHOULDER REMOVAL SQ YD	PCC BASE COURSE WIDENING 10" SQ YD
STATION / OFFSET	TO STATION / OFFSET		
STAGE I			
448+01.00 / RT 28.00'	450+08.00 / RT 28.00'		
448+01.00 / RT 32.00'	450+08.00 / RT 32.00'	90.9	90.9
457+94.00 / RT 28.00'	460+32.00 / RT 28.00'		
457+94.00 / RT 32.00'	460+32.00 / RT 32.00'	105.1	105.1
STAGE II			
448+01.00 / RT 56.00'	450+06.00 / RT 56.00'		
448+01.00 / RT 60.00'	450+06.00 / RT 60.00'	89.9	89.9
457+92.00 / RT 56.00'	460+32.00 / RT 56.00'		
457+92.00 / RT 60.00'	460+32.00 / RT 60.00'	105.3	105.3
TOTAL =		391.2	391.2

LOCATION		RRPM REFLECTOR REMOVAL	RRPM REFLECTOR REPLACEMENT
STATION	TO STATION		
440+29.44	457+31.33	EACH	EACH
440+29.44	457+31.33	22.0	22.0
TOTAL =		22.0	22.0

	CONCRETE REMOVAL CU. YD.	PERFORMED JOINT STRIP SEAL FOOT	CONCRETE SUPERSTRUCTURE CU. YD.	REINFORCEMENT BARS, EPOXY COATED POUND	BAR SPLICERS EACH	ELASTOMERIC BEARING ASSEMBLY, TYPE I EACH	ELASTOMERIC BEARING ASSEMBLY, TYPE II EACH	FURNISHING AND ERECTING STRUCTURAL STEEL POUND	JACK AND REMOVE EXISTING BEARINGS EACH	ANCHOR BOLTS, 1" EACH
STAGE I	4.7	42.8	4.9	809	12.0	3.0	3.0	656.0	6.0	12.0
STAGE II	7.6	42.8	7.7	887	12.0	4.0	4.0	874.0	8.0	16.0
TOTAL =	12.3	86.0	12.6	1700.0	24.0	14.0	14.0	1530.0	14.0	28.0

LOCATION		DISCRIPTION PAVEMENT MARKING STRIPE	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 4"
STATION / OFFSET	TO STATION / OFFSET			
STAGE I				
440+29.44 / RT 56.00'	450+29.44 / RT 40.50'	SOLID WHITE	FOOT	FOOT
450+29.44 / RT 40.50'	455+29.44 / RT 40.50'	SOLID WHITE	989.6	
455+29.44 / RT 40.50'	457+31.33 / RT 40.50'	SOLID WHITE	495.6	
448+01.00 / RT 32.00'	450+29.44 / RT 28.50'	SOLID YELLOW	200.1	
450+29.44 / RT 28.50'	455+29.44 / RT 28.50'	SOLID YELLOW	227.0	
455+29.44 / RT 28.50'	457+31.33 / RT 28.50'	SOLID YELLOW	496.8	
457+31.33 / RT 28.50'	460+32.00 / RT 32.00'	SOLID YELLOW	200.6	
457+31.33 / RT 28.50'	460+32.00 / RT 32.00'	SOLID YELLOW	298.7	
STAGE II				
440+29.26 / RT 32.00'	450+29.26 / RT 47.50'	SOLID YELLOW	991.5	
450+29.26 / RT 47.50'	455+29.26 / RT 47.50'	SOLID YELLOW	494.8	
455+29.26 / RT 47.50'	457+31.33 / RT 47.50'	SOLID YELLOW	200.0	
448+01.00 / RT 56.00'	450+29.26 / RT 59.50'	SOLID WHITE	225.2	
450+29.26 / RT 59.50'	455+29.26 / RT 59.50'	SOLID WHITE	493.6	
455+29.26 / RT 59.50'	457+31.33 / RT 59.50'	SOLID WHITE	199.4	
457+31.33 / RT 59.50'	460+32.00 / RT 56.00'	SOLID WHITE	296.9	
448+01.00 / RT 32.00'	460+32.00 / RT 32.00'	SOLID YELLOW		1231.0
440+29.44 / RT 44.00'	457+31.33 / RT 44.00'	SKIP DASH WHITE		425.5
448+01.00 / RT 56.00'	460+32.00 / RT 56.00'	SOLID WHITE		1231.0
TOTAL =			5809.8	2887.5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
SN 026-0013
 SCALE: VERT. DATE
 HORIZ. DRAWN BY
 CHECKED BY

DATE
 FILE NAME
 PLOT SCALE
 USER