

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	**	18	7
STA. TO STA.				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- D-7 JOINT REPAIRS 2007-1
- ** FAYETTE



TRAFFIC CONTROL STAGE I STRUCTURE NUMBER 026-0013

78300100 PAVEMENT MARKING REMOVAL

STATION	TO	STATION	TYPE	FEET	SQ FT
EB LANE					
440+29.44		457+31.33	4" SKIP DASH	425.5	141.8
448+01.00		460+32.00	4" SOLID	1231.0	410.3
				TOTAL = 552.1	

35400500 PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"

STATION / OFFSET	TO	STATION / OFFSET	SQ YD
EB LANE			
448+01.00 / RT 28.00'		450+08.00 / RT 28.00'	
448+01.00 / RT 32.00'		450+08.00 / RT 32.00'	90.9
457+94.00 / RT 28.00'		460+32.00 / RT 28.00'	
457+94.00 / RT 32.00'		460+32.00 / RT 32.00'	105.1
			TOTAL 196.0

X0322050 RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL

STATION	TO	STATION	EACH
440+29.44		457+31.33	22.0
			TOTAL = 22.0

70300625 TEMPORARY PAINT PAVEMENT MARKING LINE 4"

STATION / OFFSET	TO	STATION / OFFSET	STRIPE	FEET
EB LANE				
440+29.44 / RT 56.00'		450+29.44 / RT 40.50'	SOLID WHITE	989.6
450+29.44 / RT 40.50'		455+29.44 / RT 40.50'	SOLID WHITE	495.6
455+29.44 / RT 40.50'		457+31.33 / RT 40.50'	SOLID WHITE	200.1
448+01.00 / RT 32.00'		450+29.44 / RT 28.50'	SOLID YELLOW	227.0
450+29.44 / RT 28.50'		455+29.44 / RT 28.50'	SOLID YELLOW	496.8
455+29.44 / RT 28.50'		457+31.33 / RT 28.50'	SOLID YELLOW	200.6
457+31.33 / RT 28.50'		460+32.00 / RT 32.00'	SOLID YELLOW	298.7
				TOTAL = 2908.4

44004250 PAVED SHOULDER REMOVAL

STATION / OFFSET	TO	STATION / OFFSET	SQ YD
EB LANE			
448+01.00 / RT 28.00'		450+08.00 / RT 28.00'	
448+01.00 / RT 32.00'		450+08.00 / RT 32.00'	90.9
457+94.00 / RT 28.00'		460+32.00 / RT 28.00'	
457+94.00 / RT 32.00'		460+32.00 / RT 32.00'	105.1
			TOTAL 196.0

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

STATION / OFFSET	TO	STATION / OFFSET	STRIPE	FEET	SQ FT
EB LANE					
440+29.44 / RT 56.00'		450+29.44 / RT 40.50'	SOLID WHITE	989.6	329.9
450+29.44 / RT 40.50'		455+29.44 / RT 40.50'	SOLID WHITE	495.6	165.2
455+29.44 / RT 40.50'		457+31.33 / RT 40.50'	SOLID WHITE	200.1	66.7
448+01.00 / RT 32.00'		450+29.44 / RT 28.50'	SOLID YELLOW	227.0	75.7
450+29.44 / RT 28.50'		455+29.44 / RT 28.50'	SOLID YELLOW	496.8	165.6
455+29.44 / RT 28.50'		457+31.33 / RT 28.50'	SOLID YELLOW	200.6	66.7
457+31.33 / RT 28.50'		460+32.00 / RT 32.00'	SOLID YELLOW	298.7	99.6
				TOTAL = 969.4	

NOTES:
 TRAFFIC DETAILS NOT SHOWN ARE TO CONFORM WITH STANDARD 701400, 701402, AND 701406.
 MESSAGE BOARD MAY BE ADJUSTED TO MEET FIELD CONDITIONS.
 RESIDENT ENGINEER AND TRAFFIC CONTROL SUPERVISOR WILL PROVIDE THE APPROPRIATE MESSAGE FOR THE CHANGEABLE MESSAGE SIGN.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL STAGE I SN 026-0013

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 08/15/07
 FILE NAME = 026-0013
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = JUSER

MATCHLINE STA 450+49.32

