CONTRACT NO. 74198

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	12	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* VARIOUS
** D-7 PAVT PATCHING 2007-2
*** VARIOUS

Location #1: I-57, North of Effingham

Patch Number	Lane	Mile Post	CLASS A PATCHES, 10 INCH Length (FT)	Width (FT)	Type 1 (SQ YD)	Type 2 (SQ YD)	Type 3 (SQ YD)	Type 4 (SQ YD)	Tie Bars (EA)	Patching Reinf (SQ YD)	Saw Cut (FT)	Barricade (EA)
1	NBDL	164.201	6	13		8.7				8.7	65.5	
2	NBDL	164.214	6	13		8.7				8.7	65.5	
3	NBDL	164.265	6	13		8.7				8.7	65.5	
4	NBDL	164.56	6	6.5	4.3					4.3	39.5	2
5	NBDL	164.72	6	13		8.7				8.7	65.5	
6	NBDL	164.791	6	6.5	4.3					4.3	39.5	
7	NBDL	164.806	6	6.5	4.3					4.3	39.5	
8	NBDL	164.812	8	6.5		5.8				5.8	43.5	
9	NBDL	165.183	6	13		8.7				8.7	65.5	4
10	NBDL	165.186	6	13		8.7				8.7	65.5	
11	NBDL	165.294	6	6.5	4.3					4.3	39.5	
12	NBDL	165.503	6	6.5	4.3					4.3	39.5	
13	NBDL	165.538	12	13			17.3			17.3	77.5	
14	NBDL	166.122	6	6.5	4.3					4.3	39.5	12
15	NBDL	166.17	10	13		14.4				14.4	73.5	
16	NBDL	166.416	6	13		8.7				8.7	65.5	
17	NBDL	166.503	10	13		14.4				14.4	73.5	
18	NBPL	166.773	6	6.5	4.3					4.3	39.5	
19	NBDL	166.788	10	6.5		7.2				7.2	47.5	
20	NBDL	166.797	6	6.5	4.3					4.3	39.5	
21	NBDL	166.817	6	6.5	4.3					4.3	39.5	
22	NBDL	166.822	6	6.5	4.3					4.3	39.5	
23	NBDL	166.942	6	6.5	4.3					4.3	39.5	
24	NBDL	167.269	6	6.5	4.3					4.3	39.5	3
25	NBDL	167.605	6	6.5	4.3					4.3	39.5	3
26	NBDL	167.623	6	6.5	4.3					4.3	39.5	
27	NBDL	167.629	6	6.5	4.3					4.3	39.5	
28	NBDL	167.633	8	13		11.6				11.6	69.5	
29	NBDL	167.641	6	13		8.7				8.7	65.5	
30	NBDL	167.658	6	6.5	4.3					4.3	39.5	
31	NBDL	167.661	6	6.5	4.3					4.3	39.5	
32	NBDL	167.673	6	6.5	4.3					4.3	39.5	
33	NBDL	167.675	15	6.5		10.8				10.8	57.5	
34	NBDL	167.683	6	6.5	4.3					4.3	39.5	
35	NBDL	167.689	6	6.5	4.3					4.3	39.5	
36	NBDL	168.254	12	13			17.3			17.3	77.5	11
			TOTALS =		86.0	133.8	34.6	0.0	0.0	254.4	1834.0	35.0
37	SBDL	168.284	6	13		8.7				8.7	65.5	
38	SBDL	166.812	6	6.5	4.3					4.3	39.5	45
39	SBDL	166.709	10	6.5		7.2				7.2	47.5	
40	SBDL	166.67	15	6.5		10.8				10.8	57.5	
41	SBDL	166.663	6	13		8.7				8.7	65.5	
42	SBDL	165.573	6	6.5	4.3					4.3	39.5	31
43	SBDL	165.561	15	13			21.7			21.7	83.5	
44	SBDL	165.554	6	6.5	4.3					4.3	39.5	
45	SBDL	165.542	6	13		8.7				8.7	65.5	
46	SBDL	165.51	10	6.5		7.2				7.2	47.5	
47	SBDL	165.493	25	13				36.1	12.0	36.1	103.5	
48	SBDL	165.449	6	6.5	4.3					4.3	39.5	
49	SBDL	165.436	12	6.5		8.7				8.7	51.5	
50	SBDL	165.277	15	6.5		10.8				10.8	57.5	
51	SBDL	165.262	6	6.5	4.3					4.3	39.5	
52	SBDL	165.252	12	6.5		8.7				8.7	51.5	
53	SBDL	164.746	6	6.5	4.3					4.3	39.5	9
54	SBDL	164.593	8	6.5		5.8				5.8	43.5	
55	SBDL	164.575	15	6.5		10.8				10.8	57.5	
56	SBDL	164.569	6	13		8.7				8.7	65.5	
57	SBDL	164.566	6	13		8.7				8.7	65.5	
58	SBDL	164.49	12	6.5		8.7				8.7	51.5	
59	SBDL	164.463	6	13		8.7				8.7	65.5	
			TOTALS =		25.8	130.9	21.7	36.1	12.0	214.5	1282.5	85.0

Location #2, I-57, South of Effingham

Patch Number	Lane	Sta	CLASS B PATCHES, 15 INCH Length (FT)	Width (FT)	Type 1 (SQ YD)	Type 2 (SQ YD)	Type 3 (SQ YD)	Type 4 (SQ YD)	Tie Bars (EA)	Pavement Fabric (SQ YD)	Saw Cut (FT)	Dowel (EA)
1	SBDL	150.341	6	12		8.0					48.0	20.0
2	SBDL	150.332	6	12		8.0					48.0	20.0
3	SBDL	150.322	6	12		8.0					48.0	20.0
4	SBDL	150.304	6	12		8.0					48.0	20.0
5	SBDL	150.299	6	12		8.0					48.0	20.0
		TOTALS =			0.0	40.0	0.0	0.0	0.0	0.0	240.0	100.0

Patch Number	Lane	Sta	CLASS A PATCHES, 15 INCH Length (FT)	Width (FT)	Type 1 (SQ YD)	Type 2 (SQ YD)	Type 3 (SQ YD)	Type 4 (SQ YD)	Tie Bars (EA)	Patching Reinf (SQ YD)	Saw Cut (FT)	Barricade (EA)
6	SBDL	150.131	6	12		8				8	61.5	
7	SBPL	150.131	6	12		8				8	61.5	
8	SBDL	148.162	6	6	4					4	37.5	63
10	SBDL	146.239	6	12		8				8	61.5	62
11	SBDL	142.72	10	12		13.3				13.3	69.5	
12	SBDL	142.709	10	12		13.3				13.3	69.5	
13	SBDL	142.7	6	12		8				8	61.5	
14	SBDL	139.11	6	12		8				8	61.5	
15	SBDL	139.09	6	12		8				8	61.5	
16	SBDL	138.978	12	12			16			16	73.5	
17	SBDL	135.814	6	12		8				8	61.5	109
18	NBDL	143.888	6	12		8				8	61.5	
19	NBDL	144.05	6	12		8				8	61.5	
20	NBDL	144.088	6	12		8				8	61.5	
21	NBDL	144.214	10	6		6.7				6.7	45.5	
22	NBDL	144.86	6	6	4					4	37.5	
23	NBDL	147.75	6	12		8				8	61.5	
24	NBDL	147.953	6	6	4					4	37.5	
25	NBDL	147.961	6	6	4					4	37.5	
26	NBDL	147.984	10	6		6.7				6.7	45.5	
27	NBDL	147.986	12	12			16			16	73.5	
28	NBDL	147.992	6	12		8				8	61.5	
29	NBDL	147.995	10	6		6.7				6.7	45.5	
		TOTALS =			16.0	142.7	32.0	0.0	0.0	190.7	1310.5	234.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 3/12/2007
FILE NAME = c:\projects\74198d\shtsch_74198.dgn
PLOT SCALE = 58.8080 ' / IN.
USER NAME = swarters