

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	137BR	BOND	29	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X028-2A 20% STATE 80% FEDERAL	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	60	60	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	24	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	421	421	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	80	80	
20201550	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	32	32	
20300100	CHANNEL EXCAVATION	CU YD	42	42	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	80	80	
28100107	STONE RIPRAP, CLASS A4	SQ YD	346	346	
28200200	FILTER FABRIC	SQ YD	346	346	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	561	561	
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	168	168	
44000100	PAVEMENT REMOVAL	SQ YD	535	535	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	30	30	
51206200	TEMPORARY SHEET PILING	SQ FT	1285	1285	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	4	4	
54021208	PRECAST CONCRETE BOX CULVERT 12' X 8' (M273)	FOOT	84	84	
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	42	42	
5421A015	PIPE CULVERTS, CLASS A, TYPE 1 15" (TEMPORARY)	FOOT	30	30	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	737.5	737.5	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75	75	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	360	360	
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	30	30	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X028-2A 20% STATE 80% FEDERAL	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	204	204	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1834	1834	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1203	1203	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	375	375	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	337.5	337.5	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1834	1834	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	611	611	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5	5	
X7200200	WIDE LOAD SIGNING	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0064505	SECTION CORNER MARKERS	EACH	1	1	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1285	1285	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	66	66	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	118	118	

PLOT DATE = 4/1/2007
 PLOT SCALE = 24.000 / IN.
 REFERENCE = #REF#

Rev

* SPECIALTY ITEMS