

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	120R-1	ST. CLAIR	74	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*FAP 592/FAU 9251

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000 90% FED 10% STATE	-----	-----
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	115	115		
20200100	EARTH EXCAVATION	CU YD	1390	1390		
20400800	FURNISHED EXCAVATION	CU YD	3121	3121		
20800150	TRENCH BACKFILL	CU YD	160	160		
25000115	SEEDING, CLASS 1B	ACRE	0.25	0.25		
25000210	SEEDING, CLASS 2A	ACRE	1.5	1.5		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	160	160		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	160	160		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	160	160		
25100115	MULCH, METHOD 2	ACRE	3	3		
25100630	EROSION CONTROL BLANKET	SQ YD	450	450		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	405	405		
28000300	TEMPORARY DITCH CHECKS	EACH	10	10		
28000400	PERIMETER EROSION BARRIER	FOOT	650	650		
28000500	INLET AND PIPE PROTECTION	EACH	6	6		
28100107	STONE RIPRAP, CLASS A4	SQ YD	24	24		
28200200	FILTER FABRIC	SQ YD	24	24		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	5682	5682		
31001500	LIME	TON	110	110		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	297	297		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	631	631		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.7	1.7		
40600300	AGGREGATE (PRIME COAT)	TON	9	9		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	247	247		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	447	447		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	115	115		
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	3200	3200		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	108	108		
42001300	PROTECTIVE COAT	SQ YD	633	633		
44000100	PAVEMENT REMOVAL	SQ YD	3469	3469		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	75	75		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	869	869		
50105220	PIPE CULVERT REMOVAL	FOOT	137	137		
54213450	END SECTIONS 15"	EACH	4	4		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000 90% FED 10% STATE	-----	-----
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	62	62		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	459	459		
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1		
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	12	12		
60602500	CONCRETE GUTTER, TYPE A	FOOT	550	550		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	251	251		
60605805	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.06 (SPECIAL)	FOOT	268	268		
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	307	307		
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	352	352		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	833	833		
60620400	CONCRETE MEDIAN, TYPE SB-9.06	SQ FT	349	349		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	112.5	112.5		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	350	350		
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	10	10		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	10	10		
67000200	ENGINEER'S FIELD OFFICE, TYPE A	EACH	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	200	200		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	28	28		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3808	3808		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	285	285		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	129	129		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1655	1655		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	280	280		

*SPECIALTY ITEMS

Rev.

PLOT DATE = 3/22/2007
 PLOT NAME = I:\1000\1000\1000\1000\1000.dgn
 PLOT SCALE = 49.9999 / IN.
 REFERENCE = #REF#