

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	120R-1	ST. CLAIR	74	9
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		
*FAP 592/FAU 9251				

# PAVEMENT SCHEDULE

LOCATION			BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	HOT-MIX ASPHALT BINDER COURSE	HOT-MIX ASPHALT SURFACE COURSE	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 14"	HOT-MIX ASPHALT SHOULDERS 8"	SUB-BASE GRANULAR MATERIAL TYPE C	STRIP REFLECTIVE CRACK CONTROL
STA	TO	STA	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(FOOT)
<b>IL 13 (RT)</b>										
416+44.00	TO	416+74.00	0.02	0.12	14	4				
416+74.00	TO	418+17.63	0.12	0.58	65	17		64		
418+17.63	TO	418+91.50	0.08	0.34	39	10		33		75.00
418+91.50	TO	420+07.26	0.06	0.28			185	52	35	
420+07.26	TO	420+38.84	0.01	0.07			45	15	10	
420+38.84	TO	420+78.49	0.02	0.11			76	18	12	
420+78.49	TO	421+06.38	0.01	0.07			45	13	9	
422+09.16	TO	422+50.10	0.03	0.12			82	19	8	
422+50.10	TO	423+15.46	0.05	0.22			145	12	13	
423+15.46	TO	423+50.00	0.02	0.08			55	7	7	
423+50.00	TO	424+40.00	0.08	0.42	47	12				
<b>IL 13 (LT)</b>										
416+44.00	TO	418+91.50	0.20	1.00	111	28		110		
418+91.50	TO	419+88.00	0.05	0.44			145	43	18	
419+88.00	TO	420+07.26	0.01	0.07			45	9	4	
420+07.26	TO	420+75.98	0.05	0.23			155	31	13	
420+75.98	TO	421+07.06	0.03	0.12			81	14	6	
422+08.50	TO	422+46.39	0.02	0.07			49	17	8	
422+46.39	TO	423+15.45	0.05	0.23			155	31	13	
423+15.45	TO	423+50.05	0.02	0.08			56	6	7	
423+50.05	TO	424+40.00	0.08	0.42	47	12				
<b>IL 157 (RT)</b>										
1273+52.41	TO	1273+93.33	0.02	0.09			61	19	13	
1273+93.33	TO	1274+56.27	0.05	0.23			150	28	19	
1274+56.27	TO	1275+00.00	0.02	0.1			65	20	13	
1275+00.00	TO	1276+05.00	0.04	0.21	48	12		47		
1276+05.00	TO	1276+35.00	0.02	0.12	14	4				
<b>IL 157 (LT)</b>										
1273+51.67	TO	1273+90.00	0.02	0.07			48	18	8	
1273+90.00	TO	1274+56.27	0.05	0.23			150	30	13	
1274+56.27	TO	1275+00.00	0.02	0.1			65	20	9	
1275+00.00	TO	1276+05.00	0.04	0.21	48	12		47		
1276+05.00	TO	1276+35.00	0.02	0.12	14	4				
<b>CIRCLE</b>										
1+00.00	TO	2+00.00	0.12	0.59			395	45	19	
2+00.00	TO	3+00.00	0.12	0.59			395	45	19	
3+00.00	TO	4+00.00	0.12	0.59			395	45	19	
4+00.00	TO	4+08.21	0.01	0.06			42	4	2	
<b>TEMPORARY PAVEMENT</b>										
							141			
<b>TOTAL =</b>			1.7	9	447	115	3226	855	297	75

# MODIFIED SOILS

LOCATION			PROCESSING MODIFIED SOIL 12"	LIME
STA	TO	STA	(SQ YD)	(TON)
<b>EAST LEG</b>				
416+44.00	TO	418+91.50	220	4.24
418+91.50	TO	420+87.96	1485	28.60
<b>WEST LEG</b>				
422+35.96	TO	422+75.00	727	14.00
422+75.00	TO	423+50.00	366	7.05
423+50.00	TO	424+40.00	52	1.00
<b>NORTH LEG</b>				
1273+79.41	TO	1275+00.00	1009	19.43
<b>CIRCLE</b>			1823	35.11
<b>TOTAL</b>			5682	110

# ENTRANCES

LOCATION	INCIDENTAL HOT-MIX SURFACING	AGGREGATE BASE COURSE, TYPE B 8"
STATION	(TON)	(SQ YD)
<b>IL 13</b>		
418+47.46	4	21
418+51.15	28	164
*419+47.52	51	299
<b>IL 157</b>		
1275+34.66	8	47
1275+69.55	12	71
1275+83.48	5	29
<b>TOTAL</b>		
	108	631

\*FOUR CORNERS ROAD

PLOT DATE = 4/6/2007  
 FILE NAME = c:\projects\1108005\plan\1108005.dgn  
 PLOT SCALE = 48/9999 / IN  
 USER NAME = gmcainejrn

REVISIONS		DATE
NAME		

ILLINOIS DEPARTMENT OF TRANSPORTATION

**MISCELLANEOUS SCHEDULES**

FAP ROUTE 592/FAU 9251  
 SECTION 120R-1  
 ST. CLAIR COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_