

Raised Pavement Markers

Station		Notes or Direction	Complete Unit Removal and Replacement			
From	To		Removal (Each)	One-Way White (Each)	One-Way Amber (Each)	Two-Way Amber (Each)
Chain of Rocks Road						
30+64	32+50	Westbound Lane Line	5	5		
30+64	36+52	Centerline and Gore Area	25		16	9
33+90	35+25	Eastbound Lane Line		4		
IL111 - Northbound & Southbound						
204+85	207+35	Northbound - Left Turn Lane Line	7	7		
204+00	207+35	Northbound - Lane Line	6	6		
208+31	210+46	SB - Left Turn Lane Line	7	7		
208+31	213+44	Southbound - Lane Lines	6	6		
Totals -			56	35	16	9

* Reflectors removed and replaced due to Traffic Control Conflict.

Thermoplastic Pavement Marking Schedule

Station		Notes or Direction	Single White - 4" Lin. Ft.	Single Yellow-4" Lin. Ft.	Skip-Dash White - 4" Lin. Ft.	Single White - 24" Lin. Ft.	Symbols White Sq. Ft.	Short-Term Pavement Marking	Pavement Marking Removal
From	To							Tape Lin. Ft.	Sq. Ft.
Northbound & Southbound IL111									
204+85	207+35	Lane Line for Left Turn Lane	250						
208+31		Stop Bar				44	78	26	
208+08	213+44	Left Edge of Pavement		544			120	40	
208+00	213+44	Right Edge of Pavement & Lane Lines	544		140				
208+31	210+46	Lane Line for Left Turn Lane	215				86	29	
Totals -			1009	544	140	44	47	284	95
Grand Total for 4" Line Markings -			1693.0						

Epoxy Pavement Marking Schedule

Station		Notes or Direction	Single White - 4" Lin. Ft.	Skip-Dash White - 4" Lin. Ft.	Double Yellow - 4" Lin. Ft.	Diagonal * Yellow 12" Lin. Ft.	Single White - 24" Lin. Ft.	Symbols White Sq. Ft.	Short-Term Pavement Marking	Pavement Marking Removal
From	To								Tape Lin. Ft.	Sq. Ft.
Chain of Rocks Road										
30+64		Stop Bar					32	128	43	
30+60	31+25	WB Edge of Pavement	65							
31+83	33+00	WB Edge of Pavement	117							
33+75	36+52	WB Edge of Pavement	277							
30+64	32+50	Lane Line	186				47	60	20	
32+50	34+50	Left Turn Lane Taper		50				48	16	
30+60	36+52	EB Centerline			592			90	30	
32+50	36+40	Centerline Gore Area (Addition to Centerline)			390	85		90	30	
30+60	32+85	EB Edge of Pavement	225							
32+85	33+90	EB Right Turn Lane Taper		26				50	17	
33+90	35+25	EB Right Turn Lane - Lane Line	135					50	17	
33+90	35+25	EB Right Turn Lane - Edge of Pavement	135				31			
Northbound IL111										
202+95	207+35	Skip Dash		110				48	16	
202+95	207+35	Edge of Pavement	440					96	32	
207+35		Stop Bar					33	66	22	
Totals -			1580	186	982	85	65	78	726	242
Grand Total for 4" Line Markings -			2748.0							

PLAN
 NO. _____
 DATE _____
 BY _____
 CHECKED _____
 DESIGNED _____
 DRAWN _____
 PLOTTED _____
 PRINTED _____
 FILE NAME _____

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES

 FAP ROUTE 582
 SECTION 6-31
 MADISON COUNTY

DRAWN BY:

PLOT DATE: 4/21/2007

126
 2007
 10/10/07