

SCHEDULE OF QUANTITIES - LOCATIONS #1 AND #2

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				1000 LOCATION #1	1000 LOCATION #2
	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.2	6	0.2
	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	53.5	19.2	34.3
	AGGREGATE (PRIME COAT)	TON	457	122	335
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	24		24
	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	512	128	384
	TEMPORARY RAMP	SO YD	488	128	360
	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	62617	16378	46239
	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	2817	2817	
	CLASS A PATCHES, TYPE II, 11 INCH	SO YD	60		60
	CLASS A PATCHES, TYPE III, 11 INCH	SO YD	61		61
	CLASS A PATCHES, TYPE IV, 11 INCH	SO YD	658		658
	CLASS A PATCHES, TYPE II, 14 INCH	SO YD	29		29
	CLASS A PATCHES, TYPE III, 14 INCH	SO YD	54		54
	CLASS A PATCHES, TYPE IV, 14 INCH	SO YD	225		225
	CLASS B PATCHES, TYPE I, 10 INCH	SO YD	34.7	34.7	
	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	562	562	
	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	74	74	
	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	143	143	
	PATCHING REINFORCEMENT	SO YD	1066		1066
	PAVEMENT FABRIC	SO YD	216	216	
	SAW CUTS	FOOT	6472	3150	3322
	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3774	3774	
	CRACK ROUTING (PAVEMENT)	FOOT	193580	95912	97668
	CRACK FILLING	POUND	71412	31471	39941
	AGGREGATE SHOULDERS, TYPE B	TON	1092	538	554
	HOT-MIX ASPHALT SHOULDERS, 2"	SO YD	2817	2817	
	HOT-MIX ASPHALT SHOULDERS, 3 3/4"	SO YD	59168	16378	42790
	FRENCH DRAINS	CU YD	20		20
	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
	MOBILIZATION	L SUM	0.6	0.3	0.3
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	16	8	8
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	0.6	0.3	0.3

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				1000 LOCATION #1	1000 LOCATION #2
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	0.6	0.3	0.3
	CHANGEABLE MESSAGE SIGN	CAL MO	2	1	1
	SHORT-TERM PAVEMENT MARKING	FOOT	10288	5904	4324
	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	98551	37287	61264
	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1266	1266	
	PAINT PAVEMENT MARKING - LINE 4"	FOOT	94910	35987	58923
	PAINT PAVEMENT MARKING - LINE 8"	FOOT	3641	1300	2341
	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1758	492	1266
	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1758	492	1266
	MATERIAL TRANSFER DEVICE	TON	1623	369	1254
	DETOUR SIGNING	L SUM	1	0.5	0.5
	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	650	148	502
	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	973	221	752
	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING) 2"	SO YD	4507	4507	
	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING)	SO YD	76328	8635	67693
	PARTIAL DEPTH PATCHING	TON	274	194	80
	PARTIAL DEPTH REMOVAL 2"	SO YD	2439	1728	711
	DOWEL BARS 1 1/2"	EACH	1528	1528	
	TIE BARS 3/4"	EACH	193		193